



**DELHI DEVELOPMENT AUTHORITY
OFFICE OF THE EXECUTIVE ENGINEER
ELECTRICAL DIVISION No. – 4.**

F 3 (15) A / C / EL. D – 4 / DDA / 2008 – 09 / 897

Dated 30.06.2008

M/s N. K. Engg. Works
G – 15, Pocket 2, Naryana Vihar,
New Delhi – 110028.

SUB : Dev. of Area near Amusement park at Gate no. – 4, at Swarnjayanti park , Rohini.
SH : Supply and laying of cable and supply & installation of feeder pillar.
NIT No. : 10 / EE / El. D – 4 / DDA / 2008 – 09.

Dear Sir,

Your quoted item rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority as under: -

- | | |
|--------------------------|---|
| 1. Estimated Cost | : Rs. 4,74,931.00 (Rs. Four lacs seventy four thousand nine hundred thirty one only). |
| 2. Tendered Amount | : Rs. 3,28,083.00 (Rs. Three lacs twenty eight thousand eighty three only) |
| 3. Contractor's % age | : 30.92 % below the estimated cost. |
| 4. Time allowed | : One months. |
| 5. Security Deposit | : 05% of the tendered amount. |
| 6. Performance Guarantee | : 05% of the tendered amount |
- Vide FDR No. 150100PR00054338 dt. 26/06/08 of Punjab National Bank for Rs 17,000.00 valid upto 26/12/08.

You are requested to attend the office of the undersigned alongwith on non-judicial stamp paper worth Rs. 50/- to complete formal agreement within seven days from the date of issue of this letter failing which the award of work is likely to be withdrawn and the entire amount of your earnest money shall be forfeited.

You are also directed to contact the AE (E) – II of this division and start the work at once. Please note that the time allowed for carrying out the work as entered in the tender documents shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

Yours faithfully,

Executive Engineer
Elect. Divn. – 4, DDA

Copy Forwarded to: -

1. C.E. (Elect.) / DDA
2. S.E (Elect. Circle-II / DDA
3. E. E (Electrical Division). 1,2,5 to 12, Flyover (Electrical) Division No. 1 / DDA.
4. E.E. (Electrical) / QCC / DDA
5. Dy. CAO (Rohini) / DDA.
6. F.O. (Electrical) / DDA.
7. Sr. A.O. (Works)-III / DDA
8. AAO / El. D – 4 / DDA.
9. A.E. (P) / A.E. (Electrical) 1, 3 & 4. / El. D – 4 / DDA.
10. A.E. (Electrical) II / El. D – 4 / DDA with a copy of schedule of qties & specification.
11. HC / ED – 4 / DDA.
12. Agreement copy.
13. Labour commissioner, 16, Rajpura road.
14. Commissioner sales tax, Bikrikar bhawan, ITO, New Delhi.
15. Income tax office, ITO building, New Delhi.
16. Electrical, Engineer & Contractor Association (Regd.) A-14, Mayapuri Industrial area, Ph – II, New Delhi.
17. DDA Contractor Welfare Association, near barrack no. 1, Vikas Kuteer, New Delhi
18. The Director (System),Vikas Sadan, New Delhi for information .The same has also been intimated through E-mail ddatender@dda.org.in.

Please visit DDA's website at www.dda.org.in

**EXECUTIVE ENGINEER
ELECTRICAL DIVISION – 4
D.D.A**

Revised Schedule of work

Name of work : Dev. of Area near Amusement park at Gate no. – 4, at Swarnjayanti park , Rohini.

Sub Head : Supply and laying of cable and supply & installation of feeder pillar.

NIT No. : 10 / EE / El. D – 4 / DDA / 2008 – 09.

S. No.	Description of items	Qty.	Unit	Rate	Amount
1.	Supply of 3.5 X 120 sqmm XLPE insulated (heavy duty) A l. conductor armoured power cable of 1.1KV grade i/c making connections and testing etc. as reqd	530 mtrs.	Mtr.	498.00	2,63,940.00
2.	Laying of 1 No. PVC. insulated and PVC. seathed / XLPE. power cable 1.1KV grade of size Exceeding 25 sqmm but not exceeding 120 sqmm direct in ground i/c excavations, sand, cushioning, protective covering and refilling the trench etc. as reqd.	500 mtrs.	Mtr.	60.00	30,000.00
3.	Laying of 1 No. PVC insulated and PVC seathed / XLPE. power cable 1.1KV grade of size Exceeding 25 sqmm but not exceeding 400sqmm in the existing RCC / Hume / Stoneware / Pipe as reqd.	15 mtrs.	Mtr.	15.00	225.00
4.	Supply, erection, testing and commissioning of cubical type feeder pillar of size 1100mm X 900mm X 300mm fabricated out of 2mm thick CRCA M.S. sheet with 40mm X 40mm X 6mm angle iron legs as per drg. attached and suitable to accommodate accessories i/c supply & fixing following accessories therein i/c connection, interconnection with suitable size of wire, earth connection, numbering and spray painted after a coat of zinc chromate primer as reqd. a) 125 Amp. Switch dis - connector fuse (3 pole & neutral) 2 nos. b) 4 strip 300mm long Al. Bus bar 100 Amp. Capacity duly PVC tapped/sleeved having drilled holes 6mm dia. Bolts, nuts, washers etc. as reqd. 1 set. c) Danger notice plate. 1 no.	2 sets	Set.	15,000.00	30,000.00
5.	Earthing with G.I. earth pipe 4.5 mtr. Long and 40mm dia. i/c accessories and providing massonary enclosure with cover plate having locking arrangement and watering pipe etc. as reqd. (but without charcoal or coke & salt)	2 sets	Set.	1,200.00	2,400.00
6.	Extra for using salt and charcoal / coke for pipe earth electrode etc as reqd.	2 sets	Set.	300.00	600.00
7.	Providing and fixing 25mm X 5mm G.I. strip in 40mm dia. pipe from earth electrode etc. as reqd.	3 mtrs.	Mtr.	210.00	630.00
8.	Providing and fixing 25mm X 5mm G.I. strip on surface or in recess for earth connection etc. as reqd	6 mtrs.	Mtr.	48.00	288.00
				Total	3,28,083.00

A

C

CS E.E./El. D – 4

OW

D

AAO/El. D – 4

**EXECUTIVE ENGINEER
ELECTRICAL DIVISION – 4
DDA.**