

DELHI DEVELOPMENT AUTHORITY
ENGINEERS; DWARKA
WD.8;CENTRAL NURSARY;SECTOR-5

IN LIU OF PWD-6

FORM APPLICABLE PWD-8

NOTICE INVITING TENDER

6/EE/WD-8/20A/08-09

Sealed item rate tenders are invited for the following works from the approved and eligible contractors in DDA up to 3.00 P.M. which shall be opened on the same day at 3.30 P.M. at Vikas Minar, DDA, New Delhi on indicated date by the Ex. Engineer/WD-8/DDA in the presence of intending tenderers/their authorized representatives.

The enlistment of contractors should be valid on the last date of sale of tenders.

In case both the last date of sale of tender is extended, the enlistment of contractor should be valid on the original date of sale of tenders.

In case both the last date of receipt of application and sale of tenders are extended, the enlistment of contractor should be valid on either of the two date i.e. original date of sale of tender or on the extended date of sale of tenders.

The tender documents can be obtained on any working day from the CAU/DWK., DDA & Sale counter, Vikas Minar between 11.00 A.M. to 3.00 P.M. on payment of cost of tender (non-refundable) mentioned against each work on production of valid enlistment certificate. Sale of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender documents.

The manner of submission of tender/opening of the same and entry of contractor's/their authorized representative to the place of opening shall be as provided in clause 3(a), (b) & (c) of PWD-6 forming part of the tender documents.

The earnest money should be deposited along with tender documents in Receipt Treasury Challan/C.D.R./F.D.R./D.D. of a Scheduled Bank issued in favour of Sr. A.O./CAU, Dwarka, DDA, New Delhi. It should, however, be ensured that FDR/Pay Order is valid for a period of six months or more after last date of receipt of tender. The tender of the Agency who does not enclose the earnest money in the prescribed manner shall be summarily rejected

S.No.	Name of work	Estt. Cost. E.Money	Cost of tender Time allowed	Last dt.of sale Date of opening
1.	92.12 Hect. Of land at PPK DWK Isolated pocket. SH: Filling of earth in the Park adjecant to pocket-9 Nasirpur, Dwarka. NIT No.18/EE/WD-8/08-09	Rs.3, 24,848/- Rs.6, 497/-	Rs.500/- 45 days	13.8.08 18.8.08
2.	M/o Completed Scheme At Dwarka Phase.I SH: Repair & maintenance of community Hall at Sec.8, Dwk. NIT No 17/EE/WD-8) 08-09	Rs 1,20,974.00 Rs 2419.00	Rs500/- Rs30days	13.8.08 18.8.08

Executive Engineer
Western Division-8

SCHEDULE OF QUANTITY

Name of work: - D/O 92.12 hact. of land at PPK (Dwk.), isolated pocket

S H: - Filling of earth in the park adjacent to pocket 9, Nasirpur Dwarka.

S.No.	Description of items	Qty.	Unit	Rate	Amount
1.	Carriage of earth by mechanical transport including loading, unloading and spreading at site of work for all leads and lifts and as per direction of Engineer in charge. (The earth shall be provided by the department free of cost)	2814.00	cum		

SCHEDULE OF QUANTITIES.

f work:

M/o completed scheme in Dwarka Ph-I

Repair and maintenance of Community Hall at Sector-8 Dwarka.

	Description of item.	Qty.	Unit	Rate	Amount
1.	White washing with lime to give an even shade. a) Old work.(two or more coats).	96.00 Sqm.	Sqm.		
2.	Distempering with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to given an even shade.	410.00 Sqm.	Sqm.		
3.	Finishing wall with water proofing cement paint of required shade. a) Old work(One or more coats applied @ 2.20kg./10 sqm) over priming coat of primer applied @ 0.80ltr./10 sqm. complete including cost of priming coat.	342.00 Sqm.	Sqm.		
4.	Renewing glass panes, with putty and nails wherever necessary. a) Float Glass panes of thickness 4mm.	58.00 Sqm.	Sqm.		
5.	Renewing old putty of glass panes (length)	48.00 Mtr.	Mtr.		
6	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350mm and 340x410x265mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P.brass spreaders with brass unions and G.I. clamps complete; including painting of fittings and brackets, cutting and making good the walls and floors wherever required. a) Range of two urinal basins with 5 litre white PVC automatic flushing cistern.	2 Nos.	Each		

7	<p>Providing and fixing wash basin with C.I. brackets, 15mm C.P. brass pillar taps, 52mm C.P. brass waste of standard pattern including painting of fittings and brackets, cutting and making good the walls wherever require.</p> <p>a) White vitreous China Wash basin size 550x400mm with a pair of 15mm C.P. brass pillar taps.</p>	3 Nos.	Each
8	<p>Providing and fixing water closet squatting pan (Indian type W.C. Pan) with 100mm sand cast iron P or S trap, 10 litre low level white PVC flushing cistern with manually controlled device (handle lever) conforming to IS 7231, with all fittings and fixture including cutting and making good the walls and floors where required.</p> <p>a) White vitreous china Orissa pattern W.C. pan of size 580x440mm with integral type foot rest.</p>	2 Nos.	Each
9	<p>Providing and fixing brass bib cock of approved quality</p> <p>a) 15mm nominal bore.</p>	10 Nos.	Each
10	<p>Providing and fixing brass stop cock of approved quality</p> <p>a) 15mm nominal bore.</p> <p>b) 20mm nominal bore.</p>	10 Nos. 2 Nos.	Each Each
11	<p>P/F G.I. pipe complete with GI fittings and clamps including cutting and making good the walls etc. (internal work). a) 15mm dia nominal bore.</p>	56.00 Mtr.	Mtr.
12	<p>Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI:12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank</p>	2000.00 Ltr.	Per Ltr.

13	<p>Providing and laying 60mm thick factory made cement concrete interlocking paver blocks of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer in-charge.</p>	130.00 Sqm.	Sqm.
----	---	-------------	------