

- | | | |
|----|--|------------|
| 8. | Testing of tubewell water from DJB/MCD/approved laboratory as per direction of Engineer-in-charge. | 2 No Each |
| 9. | Tarametric test for tubewell which includes all operations of testing and giving necessary result such:
i) Hydrological investigation.
ii) Collection and analysis of ground water data from existing available structure in the area.
iii) Selection of suitable site for proposed tubewell.
iv) Selection depth of borehole for maximum yield expected from the tubewell the desired yield is 1000hpm, the job rate includes all the necessary T&P mobilization, phemobilization and operations to be carried out embussion of 4 sets of reports all complete as per direction of Engineer-in-charge. The item also includes the fee paid to the expert for carrying out test and preparation of report. | 4 Nos Each |