

OFFICE OF THE EXECUTIVE ENGINEER
SOUTH EASTERN DIVISION NO:8
D.D.A NEAR PKT.A-14 KALKAJI EXTN
NEW DELHI
Tel No.26096180

No.F.8 (2)/SED: 8/A/DDA/2008-2009/ 1793-1803 Dated: 18/8/08

CORRIGENDUM

Name of work: Acquisition/protection of land(fencing of acquired Land).
SH : Providing and fixing RBT fencing with RCC Standard post around South Asian University at Maidan Garhi
Estimated cost: Rs.56,58,476.00

called

The tender for the above said work ^ vide NIT No.7/EE/SED:8/2008-2009, which was scheduled to be received upto 3.00 p.m. & opened at 3.30 p.m. on 12.8.2008 & rescheduled for opening on 19.8.2008 at 3.30 p.m. at 1st floor Press Building, DDA office, Vikas Sadan, New Delhi has been further postponed due to some technical reason. All the contractors who had purchased the tender are requested to return the tender to the tender clerk, Vikas Sadan & CAU/SEZ for correction. After necessary correction the same can be had from tender clerk, Vikas Sadan & CAU/SEZ on 22.8.2008 upto 3.00 p.m. The same shall now be opened on 26.8.2008 at 3.30 p.m. at 1st floor Press Building, DDA office, Vikas Sadan, New Delhi.

Other terms & conditions shall remain unchanged.

(O.P.Dhingra) 18/8/08
EXECUTIVE ENGINEER
SED: 8/DDA

Copy to:-

1. CE(SEZ)/DDA for kind information please.
2. SE/CC15/DDA for kind information please.
3. Sr.A.O.(CAU)/SEZ/DDA for kind information.
4. F.O. to CE(SEZ) for kind information.
5. Tender Clerk, Vikas Sadan & CAU/SEZ.
6. Notice Board, SED:8, Press Building, Vikas Sadan & CAU/SEZ
7. DDA Website www.dda.org.in along with revise schedule of quantities.

o/c.
EXECUTIVE ENGINEER 18/8/08
SED: 8/DDA

SCHEDULE OF QUANTITIES

Name of work: Acquisition/Protection of land(Fencing of acquired land)


SH : Providing and fixing R.B.T. fencing with RCC standard post around South Asian University at Maidan Garhi


S.No.	Description of items	Qty	Unit	Rate(Rs)	Amount(Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50 m. a) All kinds of soil	253.00 Cum	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level. a) 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	253.00 Cum	Cum		
3	Supplying & fixing at site precast reinforced cement concrete standard boundary posts of size 150x150mm and 3m height with M-30 grade of concrete and reinforced with 4 nos bars of 8mm dia for steel along the length and 6mm dia mild steel strips at 150mm centre to centre and with suitable hooks for the purpose of binding R.B.T. wire and including one steel plate of size 150x150x4mm at one end of the post welded with reinforcement for the purpose of welding angle iron at the top for fixing concertin coil including cost of centring and shuttering(cost of earth work in excavation,concrete works in foundation to be paid separately).	1171.00 Nos.	Each		
4	Fencing with R.C.C. posts placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of R.B.T. between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (Cost of R.C.C. posts, struts, earth work and concrete to be paid for separately.) Payment to be made per metre cost of total length of RBT wire used. a) With Reinforced barbed tape / wire.	44000.00 Metre	Metre		


S.No.	Description of items	Qty	Unit	Rate(Rs)	Amount(Rs)
5	Providing and fixing concertin coil fencing with required dia 610 mm(having 15 nos) round per 6 metre length) upto 3m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00m apart and with 9 horizontal RBT stud tied with G.I. staples and G.I. clips to retain horizontal including necessary bolts or G.I. barbed wire tied to angle iron all complete as per direction of Engineer-in-charge with reinforced barbed tape(RBT)/ Spring core(2.5mm thick) wire of high tensile strength of 165Kg/Sq.mm with tape(0.52mm thick) and weight 43.478gm/metre (cost of M.S. angle C.C. blocks shall be paid separately).	3035.00 Metre	Metre		
6	Structural steel work riveted,bolted or welded in built up section,trusses and framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	8197.00 Kg.	Kg		
7	Painting with synthetic anamel paint of approved brand and manufature to give an even shade. a) Two or more coats on new work	365.00 Sqm	Sqm		
8	Welding by gas or electric plant including transporation of plant at site etc.complete	40500.00 Cm.	Cm		
9	Earth work in surface excavation not exceeding 30cm in depth but exceeding 1.5m in width as well as 10Sqm on plan including disposal of excavated earth upto 50m and lift upto 1.5m disposed soil to be levelled and neatly dressed: a) All kinds of soil	27580.00 Sqm.	100 Sqm		
10	Earth work in excavation by mechanical means(Hydraulic excavator)/ manual means over areas(exceeding 30Cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth,lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. a) All kinds of soil	1560.00 Cum	Cum		

S.No.	Description of items	Qty	Unit	Rate(Rs)	Amount(Rs)
11	Excavation in dumped stones or malba including stacking of serviceable material and unserviceable material separately and disposal of unserviceable material lead upto 50m and lift upto 1.5m disposed material to be neatly dressed.	465.00 Cum	Cum		
12	Finishing walls with textured exterior paint of required shade a) New work(two or more coats applied @ 3.28 Liter/ 10 Sqm) over and including base coat of water proofing cement paint applied @ 2.20Kg/10 Sqm.	1854.00 Sqm.	Sqm.		
				Total	

NOTE: Cement 55.70 MT @ 5175.00 per M.T. shall be issued from DDA store at Delhi/New Delhi.


J.E.(P)/SED:8


AE(P)/SED:8


EE/SED:8 18/8/08