

Delhi Development Authority
South Eastern Division No.11


NOTICE INVITING TENDER

Sealed item rate tender are invited for the following works by the Executive Engineer/SED-11/DDA, Vikas Sadan, INA pto 3.00 P.M. on behalf of DDA from the approved contractors of appropriate class of DDA on the date mentioned below which shall be opened on the same day at 3.30 P.M. at Vikas Sadan(Press building) near INA Market, New Delhi in the presence of intending purchase of their authorized representatives.

The tender documents can be obtained on any working day from the CAU(SEZ)DDA sale counter, press building, Vikas Sadan between 11.00A.M. to 3.00P.M. on payment of cost of tenders(Non-refundable) as well as amount of Earnest money mentioned against each work on production of valid enlistment certificate and valid certificate of Registration with work contract cell of Sale Tax Deptt. Of GNCTD & Tax clearance certificate issued by the work contract cell. Sale of tender form will be stopped four days(including the date of opening) before the date fixed for the opening of tender documents

The intending tenderers may see the tender documents in the aforesaid office of DDA before giving application for the same.

S.No.	NIT.No.	Name of work	Esstt.Cost E. Money Cost of Tender	Last dt. Of sale Dt. Of opening Time allowed
1.	NIT No.68/EE/SED-11/DDA/08-09	M/O various colonies under SEZ. SH: Special repair works such as floor tile, wall tile and cup board etc. in Staff Flats at A.G.V.C.	Rs.66,832/- Rs. 1,337/- Rs. 150/-	26.09.08 29.09.08 2 Months.
2.	NIT.No.69/EE/SED-11/DDA/08-09	M/O scheme under Nazul Account-II(SEZ) SH: Repair and raising of boundary wall at Institutional area Tughlakabad..	Rs.1,67,323/- Rs. 3,346/- Rs. 500/-	-Do- -Do- 45 days


 Executive Engineer
 SED - 11: DDA
 17/9/08 17/8/08

(74435)
No.F5(66,68,69)SED-11/DDA/08-09/ 1205

Dt: 17/9/08

Copy to :

- 1.All C.Es,DDA & FO to CE(SEZ)DDA.
- 2.S.E/CC-16/DDA.
- 3.Director(System)DDA for placing it in Web Site of DDA.
- 4.AO./CAU/SEZ/DDA.
- 5.PAO(EW)DDA.
6. A.O.(W)I,DDA.
- 7.All EEs/DDA.
- 8 All AEs/SED-11/DDA
9. Chief Security Officer/DDA.
10. Tender Clerk,Centralised Tender Ooffice,Vikas Sadan.
11. The Labour Commissioner,15 Rajpur Road,New Delhi
- 12 Dy.Commissioner(work Contract)Bikri Kar Bhawan,I.T.O.,New Delhi.
- 13 The Income Tax Office(contractor Circle)I.T.O.,New Delhi.
14. Executive Engineer(Q.C)DDA,Vikas Sadan.
15. Indian Pest Control Association,Flat No.11,Alishan Banquest Complex, 40 DLF Ind.Area Kirti Ngr.
- 16.DDA Contractors Welfare Asso., Block-A,Vikas Kuteer,New Delhi.
17. DDA Contractors Asso.,40-A/E-18,Vikas Kuteer,N.Delhi
18. Secy.CPWD Contractors Asso.,Y -Shape building,I.P.Estate,New Delhi.
19. Delhi Contractors and Builders Asso.,5503,Prem Raj,Bhawan,New Chandrawal,New Delhi.
20. Delhi Contr.Welfare Asso.(R)306,Masjid Moth,Rai Sahib Mkt.NDSE,Pt.II,New Delhi.
21. Trans-Yamuna DDA Contr.Asso.,11-12,Vir Sawarkar Mkt.,Gandhi Nagar,Delhi-110031
22. East Delhi DDA Contr.Asso.(R),45/2-c,East Azad Nagar,Delhi-110051.
23. Delhi Govt.Contr.Welfare Asso.(R)174,Trivent Apptt.near Police Stn.,LVivek Vihar,Delhi.
24. DDA web site dda.tender@dda.org.in & dir system dirsystem@dda.org.in.
25. Notice Board,SED-11,DDA.

Executive Engineer
SED - 11 ; DDA

Sanjay 17/9/08
17/9/08

SCHEDULE OF QUANTITIES

Name of Work: Maintenance of Scheme under Nazul Account II (SEZ).

SH:- Repairs & Raising of boundary wall at Institutional area Tughlakabad

ESSA. Cost Rs 1,67,323/-
E.M. Rs 3,346/-
T. Allowed 45 days

S.No.	Description of Items	Qty	Unit	Rate(Rs)	Amount(Rs)
1	Demolishing stone rubble masonry manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer in charge. a) In cement mortar	3.89	Cum		
2	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 Cement : 6 Coarse sand : 12 graded stone aggregate 20mm nominal size) at plinth level with: a) Cement mortar 1:6 (1 cement: 6 coarse sand)	39.00	Cum		
3	Steel work welded in built up sections / framed work including cutting hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required. a) In gratings, frames, guard bar ladders, railings, brackets, gates & similar works.	1003	Kg		
4	P/laying in position cement concrete of specified grade excluding the cost of centering & shuttering – all work upto plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	3.00	Cum		
5	12mm cement plaster of mix. a) 1:6 (1 cement: 6 C.sand)	50.00	Sqmt		
	b) 15mm cement plaster on rough side of single or half brick wall of mix 1:6 (1 cement: 6 C.Sand)	36.00	Sqmt		
6	Finishing walls with water proofing cement paint of required shade New work (two or more coats applied @ 3.84 Kg/10 sqmt	86.00	Sqmt		

7	Centering & shuttering i/c strutting, propping etc and removal of form for a) Foundation, footings, bases of columns etc for mass concrete	5.00	Sqm		
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: a) Two or more coats on new work b) One or more coats on old work	45.00 138.00	Sqm Sqm		
9	Pointing on store work with cement mortar 1:3 (1 cement: 3 fine sand) a) Raised and cut pointing	165.00	Sqm		

NOTE: Cement 4.65 M.T @ Rs. 5175/- per M.T
shall be issued from any P.D.A Store
Delhi / New Delhi