

OFFICE OF THE EXECUTIVE ENGINEER
WESTERN DIVISION NO.13 : D.D.A.
LAKKAR MANDI:KIRTI NAGAR:N.DELHI.

No:-FB(43)A/WD-13/DDA/2009-10/ 1860

DT. 14.12.09

To,

M/S A-One Associates,
71/43, Prem Nagar,
Janak Puri, New Delhi-110058.

Sub:- M/O completed scheme under Nazul A/C-II SWZ.

SH:- Maintenance and repair of water supply system for Hort.
purpose in Priyadarshni Park at G-8 area Rajouri Garden
(under special repair).

D/Sir,

Your item rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at the rates, terms and conditions given below:-

ESTIMATED COST : Rs.3,07,842/- (Rs.Three lacs seven thousand eight hundred forty two only).

QUOTED ACCEPTED AMOUNT. : Rs.2,60,123/- (Rs.Two lacs sixty thousand one hundred twenty three only).

PERCENTAGE : The percentage to be taken for purpose of operation of clause 12 shall be 15.50% below of the rates based on DSR-2007.

You are requested to attend this office along with non-judicial stamp papers worth Rs.50/- (Rupees Fifty only) to sign the formal ——— agreement within seven days from the date of issue of this letter, failing which acceptance of tender is likely to be withdrawn and entire amount of earnest money shall be forfeited absolutely.

Please note that the date of start of execution of work shall be reckoned from 10th day after the date of issue of this letter.

Time allowed for execution of work shall be one month. You are requested to contact Asstt.Engineer-II/WD-13/DDA and start the work at once. This office letter of even No.1751 dated 26.11.09 shall also form part of the agreement.

Yours faithfully

(K.K. LALA)

E.E./WD-13/D.D.A.

SCHEDULE OF QUANTITIES

11-0-11:- W/O completed scheme under Head A/C-II SW.

Maintenance and repair of water supply system for hort. purpose in Piyadishant Park at G-8 area, Rajouri Garden. (under special scheme)

11-0-11:- Description of items.

Qty.	Unit.	Rate.	Amount.
1.			
1/0 trenching and fixing G.I. pipes complete with G.I. fittings	5.40	Mtr.	Rs. 60/-
a) 32mm dia nominal bore.			Rs. 324/-

b) 32mm dia nominal bore.	525.00	Mtr.	Rs. 180/-	Rs. 94500/-
---------------------------	--------	------	-----------	-------------

c) 50mm dia nominal bore.	536.00	Mtr.	Rs. 250/-	Rs. 134000/-
---------------------------	--------	------	-----------	--------------

Providing and fixing gun metal gate valve with G.I. wheel of approved quality (screwed end).

a) 32mm nominal bore.	18 Nos.	Each.	Rs. 500/-	Rs. 9000/-
b) 50mm nominal bore.	6 Nos.	Each.	Rs. 700/-	Rs. 4200/-

3. Constructing masonry chamber 30x30x50cm inside with 75 class designation brick work in cement mortar 1:4 (1 cement: 4 coarse sand) for stop cock, with G.I. surface box 106x166x70mm (inside) with hinged cover fixed in concrete concrete slab 120x120 mm (1 cement: 2 coarse sand) 14 graded stone aggregate 75mm nominal size) necessary excavation: foundation concrete 1:4:10 (1 cement: 4 coarse sand: 10 graded stone aggregate 75mm) and inside plastering with cement mortar 1:1 (1 cement: 1 coarse sand) 12mm thick finished with a 100mm coat of 1:2 cement concrete complete upon boundary wall with F.F.S. b.100.

24 Nos.	Each.	Rs. 400/-	Rs. 9600/-
---------	-------	-----------	------------

251624=00

4. Painting G.I. pipes and fittings with two coats of anti-corrosive bitumastic paint of approved quality.
a) 32mm dia meter pipe.

525.00 Mtr. Rs. 2/- Rs. 1050/-

b) 50mm dia meter pipe.

536.00 Mtr. Rs. 3/- Rs. 1608/-

3. Providing and filling sand of grading zone V or coarser grade allround the G.I. pipes in external work.
a) 32mm diameter pipe.

525.00 Mtr. Rs. 5/- Rs. 2625/-

b) 50mm diameter pipe.

536.00 Mtr. Rs. 6/- Rs. 3216/-

Total Rs. 260,123.00

EXECUTIVE ENGINEER
WD-13 : D.D.A.
dpr