

NAME OF WORK :- DEPOSIT WORK

SH :- RESTORATION OF FOOTPATH IN SAKET SPORTS COMPLEX TO PUSHP VIHAR

TELEPHONE EXCHANGE

Schedule of Quantities

S.No	Description of items	Qty.	Unit.	Rate.	Amount.
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. a) All kinds of soil.	68.00	cum		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	155.00	cum		
3	Disposal of surplus earth by mechanical transport including loading, unloading etc. for a lead of 5.00 k.m a) Excavated earth/malba.	155.00	cum		
4	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	73.00	cum		

Estt. Cost Rs 360303 -
B. money Rs 7206 -
T. Allowed - 20 day

**OFFICE OF THE EXECUTIVE ENGINEER
SOUTH EASTERN DIVISION No.11 DDA
VIKAS SADAN NEW DELHI**

NOTICE INVITING TENDER

Sealed item/percentage rate tender are invited for the following works on behalf of the DDA from the approved and eligible contractors of appropriate class of DDA, up to 3.00 PM on the date of opening (mentioned below), which shall be opened on the same day at 3.30 PM at 1st Floor, Press Building, Vikas Sadan, INA, New Delhi-23 by the Executive Engineer/SED-11/DDA in the presence of the contractors or their authorized representatives. Tender documents can be had on any working day from the date of circulation between 11.00AM to 3.00PM on payment of the cost of tender + D Vat (non-refundable) mentioned against each work, on production of valid enlistment certificate, certificate of registration with Works Contract Cell of Sales Tax Deptt. of the GNCTD and the clearance certificate in Form XI form CAU/SZ/DDA/ Shahpur Jat, New Delhi and Centralized Tender Office at Vikas Sadan, INA, New Delhi-23. The sale of tender will be stopped four days before the date of opening (including the date of opening).

The contractors can submit their tender in sealed envelope only up to seven days before the date of opening between 10.00AM to 5.00 PM except the date of opening when it will be up to 3.00PM. The tender can also be sent by the contractors through Registered Post, which should reach the Office of the EE/SED-11/DDA at least one day before the last date of the receipt of tenders.

The manner of submission of tender, opening of the same and entry of contractors/their representatives to the place of opening shall be as provided in clause-3(a) (b) and (c) of the PWD-6 forming part of tender documents.

The Earnest Money shall accompany the tender in the form of Call at Deposit Receipt or Demand Draft of a scheduled Bank guaranteed by the Reserve Bank of India in favour of Sr. AO/CAU/SZ/DDA. The tender of the contractor who does not enclose the earnest money in prescribed manner shall be summarily rejected.

NIT No.	Name of Work & Sub-head	Estimated Cost Earnest Money	Cost of Tender Time Allowed	Last dt. of Sale Dt. of opening
---------	-------------------------	---------------------------------	--------------------------------	------------------------------------

1. NIT.No. 71/EE/SED-11/DDA/09-10

Deposit work.

SH: Restoration of foot path in Saket Sports Complex to
Pushp vihar Telephone Exchange.

Rs. 3,60,303/-	Rs. 500/- + Vat	11.12.09
Rs. 7,206/-	20 (Twenty) days	16.12.09

S. K. Saxena
EXECUTIVE ENGINEER
SED-11/DDA

P.T.O

5	<p>Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :</p> <p>a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)</p>	76.00	cum		
6	<p>Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge.</p>	416.00	sqm		

NOTE :- Cement 10.00 M.T @ Rs. 5175=00 per M.T
 Shall be issued from any P.D.A. store Delhi/
 New Delhi