

**DELHI DEVELOPMENT AUTHORITY**  
**PRESS TENDER NOTICE No. 16/FO/SZ/09-10**

Sealed item rate tenders are invited for the following works on behalf of DDA from the approved and eligible contractors of D.D.A. upto 3.00 P.M. which shall be opened on the same day at 3.30 P.M. at Vikas Sadan, D.D.A. Office, New Delhi on the dates indicated against each work.

The enlistment of the contractor should be valid on the last date of sale of tenders.

Tender documents can be obtained on payment of Cost of Tender (non-refundable) and on production of valid enlistment Certificate from AO/CAU/SZ/ DDA and Centralized Tender Office at Vikas Sadan. The intending tenderers may see the tender documents in the aforesaid offices of DDA before giving application for the same. Earnest Money should be deposited in prescribed manner along with tender.

Sl. No.	N.I.T. No.	Name & Address of Division.	Name of Work.	Estimated Cost	Last dt. of Sale
				Earnest Money Cost of Tender.	
1	37/EE/SWD-1/ DDA/2009-10	Executive Engineer, SWD-1, DDA, Vasant Kunj, New Delhi.	M/o completed scheme of Nazual A/C-I under South Zone. SH:- Repair/maint. & white washing, oil bound distemper, painting snowcem etc. at Staff Qtrs. Munirka & Basant Enclave.	Rs. 7,24,607/- Rs. 14,492/- Rs. 500 + D. Vat @ 4%	11.12.2009 16.12.2009 06 Months.
2	38/EE/SWD-1 DDA/2009-10	-do-	-do- SH:- P/L water proofing treatment regarding terracing kota stone flooring premix carpet & misc. works at CE(Elect) office, SE(Elect) office at D-2, Vasant Kunj.	Rs. 5,76,384/- Rs. 11,528/- Rs. 500/- + D. Vat @4%.	11.12.2009 16.12.2009 02 Months
3	26/EE/SWD-4/ DDA/2009-10	Executive Engineer, SWD-4, DDA, Vasant Kunj, New Delhi.	C/O 860/830 DU's(Two rooms with lounge) on the east side of Sec-D, Pkt-6, Vasant Kunj. SH:- Providing and laying peripheral sewer line with NP3 RCC pipe in front of Pkt D-6, V. Kunj.	Rs. 7,37,840/- Rs. 14,757/- Rs. 500/- + D. Vat @4%.	11.12.2009 16.12.2009 01 Months.
4	27/EE/SWD-4/ DDA/2009-10 (Short Tender Notice).	-do-	-do- SH:- Leveling and dressing at vacant land adjoining mega housing.	Rs. 13,90,974/- Rs. 27,819/- Rs. 500/- + D. Vat @4%.	05.12.2009 09.12.2009 01 Months.
5	67/EE/SED-11/ DDA/2009-10	Executive Engineer, SED-11, DDA, Vikas Sadan, New Delhi.	D/O Millennium park along Ring Road between ISEBT Sarai Kale Khan & Bhairan Road. SH:- C/o stone wall and fencing at Shanti Stupa Millennium Park.	Rs. 6,59,019/- Rs. 13,180/- Rs. 500/- + D. Vat @4%.	11.12.2009 16.12.2009 02 Months.

Contd...P/2



# SCHEDULE OF QUANTITIES

NAME OF WORK: D/O MILLENNIUM PARK ALONG RING ROAD BETWEEN ISBT SARAI KALE KHAN &

SH

: C/o Stone walls & Fencing at Shanti Stupa.

ESSH. 687 Rs 659,019.-  
E. Money Rs 13180.-  
7. Allowed - 2 (TWD)  
month

S.No.	Description of Item.	Qty	Unit	Rate(Rs.)	Amount(Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead 50 m. (a) All kinds of soil.	51.00	Cum		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. In layers not exceeding 20cm in dept, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5m	17.00	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: (a) 1:5:10 (1 cement : 5 coarse sand: 10 graded stone aggregated 40 mm nominal size)	5.00	Cum		

- 4 Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 Cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) at plinth level with :  
a) Cement mortar 1:6 (1 Cement : 6 coarse sand)  
49.00 Cum
- 5 Coursed stone masonry with hard shiseled dressed stone (Delhi Quarty) in fondation and plinth in cement mortar 1:6(1cement: 6 coarse sand)including ruled pointing with cement mortar 1:3(1cement: 3 fine sand)complete as per direction of Engineer-in-Charge  
23.25 Cum
- 6 Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.  
a) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.  
7900.00 Kg
- 7 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:  
a) Two or more coats on new work  
113.00 Sqm



8

Providing and laying cement concrete in retaining walls, return walls, wall (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. up to floor five level, excluding the cost of centering, shuttering and finishing:

a) 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)

2.00

Cum

9

Centering and shuttering including strutting, propping etc. and removal of form work for:

a) Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.

6.00

Sqm.

NOTE:-

CEMENT 6.00 M.T @ Rs. 5175.00 per m.T shall

be issued from any D.D.A Store Delhi / New Delhi.