

**OFFICE OF THE EXECUTIVE ENGINEER
SOUTH-WESTERN DIVISION NO.8
DELHI DEVELOPMENT AUTHORITY
CENTRAL NURSERY, SECTOR-5, DWARKA**

No.F.54 (1685)/EE/SWD-8/A/2011-12/DDA/2107

Dt: 27-12-11

To

Shri Ranbir Singh Yadav,
Plot no. 45, M Block,
Gopal Nagar, Ph-II,
Najafgarh,
New Delhi-110043.

Sub: M/o various colonies under Nazul Account-II in Dwarka.
SH: Improvement of Road berm of 20m road in front of pkt. II, Sector-2, and
Bhaskaracharya college in Sector-2, Dwarka.
Ref: Intent letter no. F.54 (1685) EE/SWD-8/A/2011-12/DDA/2057 dt. 8-12-11
P.G. Received on 13-12-11 for Rs. 50000/- in the shape of FDR issued by Indian Bank,
Dwarka, Delhi.

Your item rate tender for the above mentioned work is hereby accepted on behalf of
the Delhi Development Authority at the rates, terms & conditions given below:

Estimated Cost: Rs. 955209/- (Rupees nine lacs fifty five thousand two hundred nine
only).

Quoted Amount Rs.1354408/- (Rupees thirteen lacs fifty four thousand four hundred
eight only).


Accepted Amount Rs.927592- (Rupees nine lacs twenty seven thousand five hundred
ninety two only).

The percentage to be taken for the purpose of Clause-12 of the agreement shall be
2.89% below on the rates based on DSR-2007.

You are requested to attend the office along with a non-judicial stamp paper worth
Rs.50/- (Rupees fifty only) to complete the formal agreement within seven days from the
date of issue of this letter, failing which, acceptance of tender is likely to be withdrawn and
earnest money forfeited. Your letter dated 28-11-11 also form a part of agreement.

Please note that time allowed for completion of work as entered in the tender shall be
reckoned from the 10th day after the date of issue of this letter to commence the work. The
time allowed for execution of work is two months.

You are requested to contact AE-IV of this division and start the work immediately.


EXECUTIVE ENGINEER
SWD-8/DDA

SCHEDULE OF QUANTITIES

Agency: Sh. Ranbir Singh Yadav
E/cost: Rs.955209/-
Accepted amt.: Rs.927592/-

N.O.W. : M/o various colonies under Nazul A/c-II in Dwarka

SH: Improvement of road berm of 20m road in front of pocket -2, sector-2 and Bhaskaracharya college in sector 2, Dwarka.

S.No.	Description of Item	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Earth work in surface excavation not exceeding 30.cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth upto 50m and lift up to 1.5m, disposal soil to be levelled and neatly dressed. a) All kinds of soil.	780.00	100Sqm	3090.00	24102.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	78.00	Cum	3199.00	249522.00
3	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	2.25	Cum	3178.00	7150.50
4	6 mm cement plaster of mix 1:3 (1 cement: 3 fine sand)	3.50	Sqm	105.00	367.50
5	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand)	13.00	Sqm	118.00	1534.00
6	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (1 cement: 6 fine sand)	7.00	Sqm	135.00	945.00
7	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction and of approved size and design/ shape laid in required colour and pattern over and including 50mm thick compacted bed of jamuna sand, filling the joints with jamuna sand etc. all complete as per the direction of Engineer-in-charge. (Interlocking paver blocks should be K.K. or equivalent brand as per I.S. code no. IS 658:2006)	1095.00	Sqm	465.00	509175.00
8	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and curvature jointed with cement mortar 1:3 (1 cement: 3 coarse sand) including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	7.50	Cum	6800.00	51000.00
9	Making bell mouth opening/ entrance of size 100x50x50cm for drainage pipe under footpath including providing cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size) for shape of bell mouth including plastering providing and fixing precast R.C.C./ S.F.R.C. slab including plastering with cement mortar 1:3 (1 cement : 3 fine sand) of 6 mm thickness on exposed surface of the slab & bell mouth including centring, shuttering & neat cement punning inside the bell mouth etc. all complete.	16.00	Each	1400.00	22400.00

c/o Rs.866196.00

10	Providing and fixing in position perforated or non-perforated SFRC covers 100mm thick (Heavy duty) as per direction of Engineer-in-charge.(To be engraved EE/SWD-8/Year)	18.00	Sqm	1500.00	27000.00
11	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	375.00	100sqm	480.00	1800.00
12	Disposal of earth/building rubbish /malba by mechanical transport to approved dumping ground including loading / unloading for within all lead and lifts. As per the direction of Engineer-in-charge.	156.00	Cum	51.00	7956.00
13	Providing Hydraulic (J.C.B.) inclusive of hire & running charges for clearing of Malba i/c levelling and dressing all complete as per the direction of Engineer-in-charge. Nothing extra shall be paid on account of diesel, lubricants, driver & helper etc.	4.00	days	6160.00	24640.00

Total : Rs.927592.00


 Executive Engineer,
 SWD-8/DDA