

DELHI DEVELOPMENT AUTHORITY
WESTERN DIVISION NO-8
Sector-5, Central Nursery, Dwarka
New Delhi-110075

R.A.D

No.F.81(28)Acs/WD-8/DDA/2011-12/ 1577

Dt. 05/12/12

To

M/s Unnatti Construction Co;
274, DDA Flats, Sector-1, Pocket-1.
Dwarka, New Delhi-110075.

Name of work : M/o Various colonies under Dwarka Zone Nazul A/c-II.
SH : Repair of pot holes and damaged road (10mtr R/W 13.5mtr R/W)
around SPG complex near Metro Station Sector-8, Dwarka
Ref: : Letter of intent vide No.F.81 (28)A/cs/WD-8/DDA/2011-12/1434
dt.07.11.2012
Ref of P.G.: : FDR No.773525 dt. 26.11.2012 amounting to Rs.53,611.00 of
Bank of Maharashtra. D-22/23 Institutional Area, Janak
Puri, New Delhi.

Dear Sir,

Your item rate e-tender dated 24.09.2012 for the above mentioned work has been accepted on behalf of DDA at the rates, terms and conditions given below:

1. Estt.Cost. : Rs.9,28,395.00 (Rupees Nine lac twenty eight thousand three hundred ninety five)only
2. Quoted Amount. : Rs.10,72,210.00 (Rupees Ten lac seventy two thousand two hundred ten) only;
3. Accepted Tender : Rs.10,72,210.00 (Rupees Ten lac seventy two thousand two hundred ten) only;
(As per annexure 'A')
4. Percentage for the Purpose : 15.49 % above the Estt Cost based on D.S.-2007.
5. Time allowed : 03 Months.


You are requested to attend this office to sign the agreement along with one non-judicial stamp paper worth Rs.50/- (fifty) within 7 days from the date of issue of this letter. Please note that if you fail to sign the agreement within seven days from the date of issue of this letter, of acceptance of the tender is likely to be withdrawn and the earnest money as well as performance guarantee will be forfeited.

You are also requested to contact the A.E. II of this division and start the work at once. Please note that time allowed for carrying out the work as entered in the tender form shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

VAT, Cess ,& other statutory taxes shall be deducted as applicable from time to time.

Encl: Schedule of awarded rates

Yours faithfully


Executive Engineer
Western Division-8



DELHI DEVELOPMENT AUTHORITY

Name of Work: M/O various colonies under Dwarka Zone, Nazul A/c-II

SH : Repair of Pot Holes and damaged road (10 MR/W, 13.5 M RW) Around SPG Complex near Metro Station Sec-8, Dwarka


SCHEDULE OF QUANTITIES

NIT No. :15/EE/WD-8/DDA/2012-13

Estimated Cost: Rs. 9,28,395/-

NAME OF THE FIRM			<i>Accepted Rate</i> unnatti const. co.			
S. No.	Description of Item	Qty	Unit	Rate	Rate in words	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm. on plan including disposal of excavated earth upto 50 M and lift upto 1.5 m, disposed soil to be leveled and neatly dressed.	2000.00	100/sqm	2000.00	Rupees Two Thousand Only	40000.00
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift upto 1.5 m. a) All kinds of soil.	2800.00	100/sqm	500.00	Rupees Five Hundred Only	14000.00
	Supplying and stacking at site. a) 53 mm to 22.4 mm size stone aggregate.	266.00	cum	1050.00	Rupees One Thousand Fifty Only	279300.00
4	Supplying and stacking at site. a) Stone screening 11.2 mm nominal size (Type B).	6.00	cum	900.00	Rupees Nine Hundred Only	5400.00
5	Supplying and stacking at site. a) Moorum	3.00	cum	250.00	Rupees Two Hundred Fifty Only	750.00
6	Laying spreading and compacting stone aggregate of specified sizes to WBM specifications including spreading in uniform thickness, hand picking, rolling with 3 wheeled road/ vibratory roller 8-10 tonne in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate water and compacting to the required density.	214.00	cum	200.00	Rupees Two Hundred Only	42800.00
7	Providing and applying tack coat using hot straight run bitumen, of grade 80/100 including heating to bitumen spraying of the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications: a) On W.B.M. @ 0.75 kg / sqm.	2850.00	sqm.	20.00	Rupees Twenty Only	57000.00
8	2.5 cm premix carpet surfacing with 2.25 cum and 1.12 cum of stone chippings of 13.2 mm and 11.2mm size respectively per 100 sqm. and 52 kg. and 56 kg. of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively with paver finisher including a tack coat with hot straight run bitumen including consolidation with road roller of 6 to 9 tonne capacity etc. complete. (tack coat to be paid for separately). a) With paving Asphalt 60/70 with no solvent.	2850.00	sqm.	145.00		413250.00

9	Disposal of lime morrum / building rubbish etc. by mechanical transport including loading unloading & spreading complete upto to lead of 5 Km. as per direction of Engineer in-charge	790.00	sqm.	29.00	Rupees Twenty Nine Only	22910.00
10	Filling pot holes & patch repairs with open graded premix surfacing 20 mm removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides & base of excavation as per clause 503 (Morth specification) back filling the pot holes with hot bituminous material as per clause 511, Morth specification compacting, trimming and finishing the surface to form a smooth continuous surface, all complete as per direction of Engineer in-charge.	48.00	cum	4100.00	Rupees Four Thousand One Hundred Only	196800.00
	TOTAL					1072210.00


 Engineer
 Western Division-8
 BDA