

DELHI DEVELOPMENT AUTHORITY  
WESTERN DIVISION NO-8  
Sector-5, Central Nursery, Dwarka  
New Delhi-110075

No.F.81( 29 )Acs/WD-8/DDA/2011-12/ 1579

Dt. 05/12/12

To

M/s Unnatti Construction Co;  
274, DDA Flats, Sector-1, Pocket-1.  
Dwarka, New Delhi-110075.

Name of work : M/o Various colonies under Dwarka Zone Nazul A/c-II.  
SH : Improvement of road berms, S.W. Drain & parks in Isolated Pkt.  
14. Sector-8, Dwarka.  
Ref: : Letter of intent vide No.F.81 (29 )A/cs/WD-8/DDA/2011-12/1435  
dt.07.11.2012  
Ref of P.G.: : FDR No.773524 dt. 26.11.2012 amounting to Rs.28,112.00 of  
Bank of Maharashtra. D-22/23 Institutional Area, Janak  
Puri, New Delhi.

Dear Sir,

Your item rate e-tender dated 24.09.2012 for the above mentioned work has been accepted on behalf of DDA at the rates, terms and conditions given below:

1. Estt.Cost. : Rs.5,65,408.00 (Rupees Five lac sixty five thousand four hundred eight ) only
2. Quoted Amount. : Rs.5,62,235.00 (Rupees Five lac sixty two thousand two hundred thirty five ) only;
3. Accepted Tender : Rs.5,62,235.00 (Rupees Five lac sixty two thousand two hundred thirty five ) only;  
(As per annexure 'A' )
4. Percentage for the Purpose : 0.56 % ( Zero point five six percent) below the Estt Cost based on D.S.-2007.
5. Time allowed : 02 Months.


You are requested to attend this office to sign the agreement along with one non-judicial stamp paper worth Rs.50/- (fifty) within 7 days from the date of issue of this letter. Please note that if you fail to sign the agreement within seven days from the date of issue of this letter, of acceptance of the tender is likely to be withdrawn and the earnest money as well as performance guarantee will be forfeited.

You are also requested to contact the A.E. II of this division and start the work at once. Please note that time allowed for carrying out the work as entered in the tender form shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

VAT, Cess, & other statutory taxes shall be deducted as applicable from time to time.

Encl: Schedule of awarded rates

Yours faithfully

  
Executive Engineer  
Western Division-8



## DELHI DEVELOPMENT AUTHORITY

Name of Work: M/O various colonies under Dwarka Zone, Nazul A/c-II.

SH : Improvement of Road berms, S.W. Drain & Parks in Isolated Pkt-14, Sector-8, Dwarka.

### SCHEDULE OF QUANTITIES

NIT No. :14/EE/WD-8/DDA/12-13

Estimated Cost: Rs. 5,65,408/-


*Awarded 8/8/89*

### NAME OF THE FIRM

unnatti const. co.

S. No.	Description of Item	Qty	Unit	Rate	Rate in words	Amount
1	Earth work in surface excavation not exceeding 30 cms in depth but exceeding 1.5 cm in width as well as 10 sqm. on plan including disposal of excavated earth upto 50 M and lift upto 1.5 m, disposed soil to be levelled and neatly dressed.	4200.00	100/sqm	2100.00	Rupees Two Thousand One Hundred Only	88200.00
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto to 50 m and lift upto 1.5 cm. a) All kinds of soil	3000.00	100/sqm	500.00	Rupees Five Hundred Only	15000.00
3	Desilting of S.W. drains & chambers by removing covers & placing the same in position after cleaning drains and chambers etc. removal of silt complete as per direction of Engineer in-charge.	321.00	curh.	135.00	Rupees One Hundred Thirty Five Only	43335.00
4	Brick work with cement fly ash FPS bricks of class designation 75 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand).	15.00	cum	2600.00	Rupees Two Thousand Six Hundred Only	39000.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work upto plinth level. a) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	5.00	cum	3000.00	Rupees Three Thousand Only	15000.00
6	Providing hoisting and fixing upto floor five level precast RCC in small lintels not exceeding 1.5 M clear span upto floor five level including the cost of required centering, shuttering & finishing smooth with 6 mm thick cement plaster 1:3(1 cement : 3 fine sand) on the exposed surfaces but excluding the cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone agg. 20 mm nominal size).	2.00	cum	6500.00	Rupees Six Thousand Five Hundred Only	13000.00
7	Disposal of Malba / building rubbish, sludge, moorum etc. by mechanical transport including loading, unloading and stacking complete upto a lead of 5 Km. as per direction of Engineer in-charge.	1511.00	cum	30.00	Rupees Thirty Only	45330.00
8	12 mm cement plaster of mix 1:6 (1 cement : 6 coarse sand).	70.00	sqm	70.00	Rupees Seventy Only	4900.00
9	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:6 (1 cement : 6 coarse sand).	50.00	sqm	80.00	Rupees Eighty Only	4000.00
10	Colour washing such as green, blue or buff to give an even shade on new work (two or more coats) with a base coat of white washing with lime.	120.00	sqm	9.00	Rupees Nine Only	1080.00

11	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. a) Two or more coats on new work.	8.00	sqm	50.00	Rupees Fifty Only	400.00
12	Reinforcement for RCC work including straightening, cutting, bending & placing in position and binding all complete. a) Thermo-mechanically treated bars.	200.00	kg	55.00	Rupees Fifty Five Only	11000.00
13	Filling pot holes & patch repairs with open graded premix surfacing 20 mm removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides & base of excavation as per clause 503 (month specification), back filling the pot holes with hot bituminous material as per clause 511 (month specification), compacting & finishing the surface to form a smooth continuous surface, all complete as per direction of Engineer in-charge as per clause 3004.2 (month specification).	49.00	cum	4600.00	Rupees Four Thousand Six Hundred Only	225400.00
14	Steel work welding in built up section / frame work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. a) In grating, frames, guard bar, ladder, railings, brackets, gates and similar works.	214.00	kg	60.00	Rupees Sixty Only	12840.00
15	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design / shape laid in required colour and patten over and including 50 mm thick compacted bed of fine sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	125.00	sqm	350.00	Rupees Three Hundred Fifty Only	43750.00
TOTAL						562235.00

  
 Executive Engineer  
 Western Division-8  
 DDA