

**OFFICE OF THE EXECUTIVE ENGINEER  
SOUTH-WESTERN DIVISION NO.8  
DELHI DEVELOPMENT AUTHORITY  
CENTRAL NURSERY, SECTOR-5, DWARKA**

No. F 54 (1718)/EE/SWD-8/A/12-13/DDA/ 1267

Dated: 26-12-12

To

M/S Tara Chand Sumit Construction Co.,  
55, D.D.A. Flats, Todapur,  
New Delhi-110071.

Name of work:- M/o various colonies under Nazul A/c-II in Dwarka

SH:- Improvement of service lane from metro line upto Vardhaman plaza, along sector-12,  
on M.P. Road No.219, Dwarka.

Ref:- F. 54(1718)EE/SWD-8/A/2012-13/DDA/1181 Dt: 01.12.12.

P.G. Received on:- 20.12.12. for Rs. 43032/- in the shape of FDR issued by Central Bank of India, New Delhi.

Dear Sir,

Your item rate tender for the above mentioned work is hereby accepted on behalf of the Delhi Development Authority at the rates, terms & conditions given below:


**Estimated Cost:- Rs.6,17,344/- (Rs. Six Lacs Seventy Thousand Three Hundred Forty Four Only).**  
**Quoted/tendered Amount:- Rs.8,60,647/- (Rs. Eight Lacs Sixty Thousand Six Hundred Forty Seven Only).**  
**Accepted Amount: Rs.8,60,647/- (Rs. Eight Lacs Sixty Thousand Six Hundred Forty Seven only).**

The percentage to be taken for the purpose of Clause-12 of the agreement shall 39.41 % above on the rates based on DSR-2007.

You are requested to attend the office along with a non-judicial stamp paper worth Rs.50/- (Rupees fifty only) to complete the formal agreement within seven days from the date of issue of this letter, failing which, acceptance of tender is likely to be withdrawn and earnest money forfeited.

Please note that time allowed for completion of work as entered in the tender shall be reckoned from the 10<sup>th</sup> day after the date of issue of this letter to commence the work. The time allowed for execution of work is Forty Five Days.

You are requested to contact AE-IV of this division and start the work immediately.

  
**Executive Engineer  
SWD-8/DDA**



DELHI DEVELOPMENT AUTHORITY

Name of work:- M/o Various colonies under Nazul A/C-II in Dwarka.  
Sht:- Improvement of service lane from metro line upto Vardhaman Plaza, along sector 12, on MP road no. 219, Dwarka.


SCHEDULE OF QUANTITIES  
INT No.-2/IE/SWB  
Estimated Cost: Rs. 617364/-

NAME OF THE FIRM

M/S TARA CHAND SUMIT CONST.CO.

S.No.	Description of item	Quantity	Unit	Rate.	Amount.
1	Scarifying metalled (water-bound) road surface including disposal of rubbish lead upto 50m and consolidation of the aggregate received from scarifying with power road roller of 8 to 1000mm capacity.	1262	sqm	10.00	12620.00
2	Supplying and stacking at site. a) 90 mm to 45 mm size stone aggregate. b) 55 mm to 22.4 mm size stone aggregate. c) Stone screening 13.2 mm nominal size (Type B) d) Stone screening 11.2 mm nominal size (Type B) e) Road ball.	56.11 cum 159.45 cum 4.07 cum 25.72 cum 21.21 cum	cum cum cum cum cum	1200.00 1200.00 500.00 500.00 300.00	67332.00 191340.00 2035.00 12860.00 6363.00
3	Laying spreading and compacting stone aggregate of specified sizes to WBM specifications including spreading in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne in stages to proper grade and camber, applying and becoming requisite type of screening / binding material to fill up interstices of coarse aggregate watering and compacting to the required density.	174.34	cum	300.00	52302.00
4	Finishing and applying tack coat using hot asphalt emulsion (Grade CD-103) including rolling, for rollers, spreading the binder with mechanical sprayer spray unit fitted with burner boiler, cleaning and preparing the existing road surface as per specifications. u) On W.B.M. @ 0.75 Kg / sqm.	1713.5	sqm	35.00	60007.50
	b) On bituminous surface @ 0.50 kg / sqm.	1075.5	sqm	25.00	26887.50

5	2.5 cm cement capot surfacing with 2.25 cum and 1.12 cum of stone chippings of 13.2mm and 11.2mm size respectively per 100 sqm. and 52 kg and 50 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively including a tack coat with hot straight run bitumen with the aid of hot mix plant with paver finisher including consolidation with road roller of 6 to 3 tonne capacity etc. complete. (tack coat to be paid for separately) ; a) With paving Asphalt 60/70 with no solvent	2790	sqm	138.00	385020.00
6	Providing and laying and making key channel 30cm wide and 50mm thick of cement concrete 1:3:6 (1 cement, 3 coarse sand & graded stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40 mm nominal size well rammed and consolidated and grouted with fine sand including finishing the top smooth etc. complete and as per direction of Engineer-in-charge.	400	metre	80.00	32000.00
7	Disposal of malter/building rubbish by mechanical transport to approved dumping ground including loading / unloading for all load and lifts. As per the direction of Engineer-in-charge.	158	Cum	60.00	11880.00
TOTAL					80547.00

  
 Executive Engineer  
 SWD-8, DDA