

**DELHI DEVELOPMENT AUTHORITY  
HORTICULTURE DIVISION No - X.**

No. F. 16. ( 72 )/Hort. X/DDA/2012-13/4427

Date :- 3-12-12

To,

M/S. Sh. H. R. G. Associates  
266-D-5/A, Ward No. 2  
Mehrauli, New Delhi - 30

Sub: - M/c Park plantation touch and other  
equipment as per work (Rural A/c - II)  
M/c Rej. of old orchard at Alim Wala Bagh, Shalimar Bagh.  
S/S & Droughting the existing ground, S/S & good earth, CPM,  
J. Band, R. Bajri, etc. etc. Chemical fertilizers etc.

Ref. Performance Security/Guarantee Submitted by you vide your letter

No. .... dt. 29-11-12

Dear Sir (s),

Your quoted/negotiated item rate tender for the above cited work has been accepted on  
dt. 19-12-12 behalf of Delhi Development Authority at the rates, terms & condition given below-

1. Estt. Cost. Rs. 1130538/- (Rs. Eleven Lacs thirty thousand five hundred thirty eight only)
2. Accepted Amount Rs. 771745/- (Rs. Seven Lacs seventy one thousand seven hundred forty five only)
3. Time Allowed 60 Days


You are requested to attend the office of the undersigned along with a non judicial stamp paper worth Rs. 50/- to complete the formal agreement within 7 days from the date of issue of this letter failing which the award of work shall likely to be withdrawn and the entire amount of your earnest money and performance guarantee shall be forfeited.

It may be noted that if any mistake/error in the nomenclature unit, rates of the item mentioned in the schedule attached occur inadvertently, it will not entitle for payment accordingly. The rates, unit and nomenclature will be taken as per provision of DSR 2007 for the purpose of payment.

You are also requested to contact the A.D. II./Hort. -X/DDA and start the work at once. please not that the time allowed for carrying out the work as entered in the tender document shall be reckoned from the 10th day after the issue of this letter to commence the work. Your negotiation letter dated ..... shall also form part of the agreement.

30/11/12  
DY. DIRECTOR (HORT.)  
HORT. DIVN. NO. X  
D.D.A

**Copy To :-**

1. Director (H) S.E.Z. /DDA.
2. Commissioner Sales Tax, Work contract cell I.P. Estate, New Delhi.
3. Income Tax Office I.P. Estate, New Delhi.
4. The Labour Commissioner 15 Raj pur Road, Delhi.
5. Dy. Dir. (Hort.) QAC, DDA Vikas Sadan, New Delhi.
6. All Dy. Director/Jt. Dir. (Hort.) DDA
7. Sr. A.O./CAU (NZ)DDA.
8. A.A.O./Hort./DDA.
9. A.D. (H)  /Hort. -X, he is directed to ensure the quality and quantity of work.
10. H.C. /Hort.- X/DDA
11. O/c



**DY. DIRECTOR (HORT.)**  
**HORT. DIVN. NO. X**  
**D.D.A**



**DELHI DEVELOPMENT AUTHORITY**  
**HORT. DIVISION -X**

Name of work :- M/o Park Plantation trucks & other equipments in Horticulture Wing N.A. - II  
M/O Reg. of old orchard at Ahiro wala bagh at Shalimar Bagh

Sub. Head :- Ploughing the existing ground, S/S/s good earth, CDM, jamuna Sand, Red Bajri, Preparation of beds, Digging holes, Fine dressing, Supply of Neem oil, Insecticides/pesticides, PVC Pipe, Supply of truf (gachi) of selection, Clearing grass, Removal malba, Supply of Safada ballies, Organophos, Providing and fixing of Precast Concrete Bench, Supply of plants, Supply of Chemical fertilizer etc. at site.


S.no	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs)	AMOUNT (Rs)
1	Ploughing the existing ground to a depth of 15 cm to 25 cm and watering the same. All kinds of soil	20235.00 sqm	100/ Sqm.	4600	8294000
2	Supplying and stacking of good earth at site including royalty and carriage with all leads and lifts. (Good earth measured in stacks will be reduced by 20 % for payment)	506.00	Cum.	1500	759000
3	Supplying and stacking of Cow dung manure at site including royalty and carriage with all leads and lifts (Cow dung manure measured in stacks will be reduced by 8 % for payment)	490.00	Cum.	1500	735000
4	Supplying and stacking of jamuna sand at site I/C royalty, carriage and loading /un loading for all leads and lifts.	30.00	Cum.	5000	150000
5	Supply and stacking of Red Bajri at site by mechanical transport including royalty, carriage and loading /unloading with all leads and lifts..	24.28	Cum.	10000	242800
6	Spreading of good earth, cow dung manure, Red Bajri and jamuna sand in required thickness. (Cost of good earth, cow dung manure, Red Bajri and jamuna sand to be paid separately)	687.00	Cum.	1000	687000
7	Preparation of beds for hedging and shrubbery by excavating 60 cm. deep and trenching the excavated base to a further depth of 30cm. refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 Part of stacked volume of earth after reduction by 20 %: one part of stacked volume of sludge or manure after reduction by 8%). Flooding with water filling with earth if necessary. Watering and finally fine dressing, levelling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and levelling as directed within a lead of 50 m lift upto 1.5 m. complete (cost of sludge. Manure or extra earth to be paid for separately).	750.00	Cum.	3000	2250000



8	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2: 1 by volume (2 part of stacked volume of earth after reduction by 20 %: 1 part of stacked volume of manure after reduction by 8%) flooding with water dressing including removal of rubbish and surplus earth .if any with all leads and lift (cost of manure, sludge or extra good earth if needed to paid for separately).				
i	SIZE 0.90m. dia and 0.90m. deep	500.00	Nos.	Each	500
ii	SIZE 0.60m. dia and 0.60m. deep	2200.00	Nos.	Each	1600
9	Fine dressing of the ground.	20235.00	sqm	100/ Sqm.	12141
10	supply of Neem oil Cake [in 50 kg. Bag] at site	31.00	Qtl.		24800
11	supply of Insecticides / pesticides Chlorpyrifos.20% EC.at site{ packing in 1 ltr.}	25.00	Ltr.		3750
12	Supply of P, V, G, pipe 3" dia blue colour rain forced, lay flate hose for water delivery W.P. 5 Kgf / Cm.2 at site.	360.00	Mtr		21600
13	Supply of truf (gach) of selction No. 1 grass at site size 30cm x 30cm and thickness will be 37.5 cm. also. [20235/10 = 2023 Sqm.]	2023.00	sqm	P/ Sqm.	80920
14	Clearing grass and removal of the rubbish up to a distance of 50 m. outside the periphery of the area cleared	3094.00	Sqm	100/ Sqm.	8094
15	Removal malba / garbage / building rubbish by mechanical transport I/C Carriage, Loading /unloading upto lead 5.00 km., complete as per direction of engineer-in-change.	200.00	Cum.		8000
16	Supply of Safada ballies, (Length 2.0 mt.) 125 mm dia metre at site.	200.00	Nos	Each	16000
17	Supply of Galvanised steel barbed wire at site	2.00	quint al		11000
18	Supply of Organophos in [50 kg. Packing] at site.	26.00	Qtl.		18200



19	Providing and fixing of Precast Concrete Bench [ Chair type]with back rest manufactured by using M 30 grade of concrete & reinforced suitable to prevent damage during handling transportation, erection and long use. The bench consists of 2 nos. L-Shape base support in gray cement colour of thickness of 100mm.back height 1000mm.&front height 450mm base width 620mm and 5nos. reinforced concrete planks of in red colour size 1500 x 100 x 50mm and 1no of reinforced concrete planks of size 1500 x 200 x 50 mm. All parts are joined together with galvanized nuts and bolts of suitable size. All bolts are sealed after assembly seating length of the bench 1500mm. Seating height of the bench = 450mm. Total height of the bench = 1000mm. Front face of all planks shall be given special coating to make them water proof and glossy	10.00	Nos.	Each	4500-	45000-
20 [a]	supply of Plants fully grown free from all disease at site in polythene Bags ( size 6"x9")					
i	Tree plants      Awlla Ht. 4' -0" to 4' -6" in P/Bags	300.00	Nos.	Each	30-	9000-
ii	Tree Plant      Ficus Bangamina Ht. 4' 1/2" to 5' in P/Bags	200.00	Nos	Each	30-	6000-
[b]	Supply of Shrub Plants in 6"x9" P/bags free from all disease at site					
i	Shrub Plant      Baugenvella Mixed ht. above 1'-6" and above	1000.00	Nos	Each	15-	15000-
ii	Shrub Plant      T.M.C. Chandani { Verigeted } ht. 2' and above	1200.00	Nos.	Each	15-	18000-
[c]	Supplying of well developed Hedge plants in P/ Bags free from all disease at site					
i	Hedge Plants      Karonda Red    Ht. 1'-6" and above at site	8000.00	Nos.	Each	10-	80000-
21	Supply of Chemical fertilizer at site.					
[A]	D.A.P. [FFCO / KRIBHCO - Make] at site. [ in 50 kg packing]	15.50	Qtl.		1900-	29450-
[B]	Urea [FFCO / KRIBHCO - Make] at site [ in 50 kg packing]	8.00	Qtl.		700-	5600-
Total						₹. 771745-00

  
 Dy. Director (Hort)  
 Hort Deptt. DDA  
 New Delhi