

**DELHI DEVELOPMENT AUTHORITY
HORTICULTURE DIVISION No - X.**

No. F. 16. (73)/Hort. X/DDA/2012-13/ 4429

Date: - 3-12-12

To,

M/S. Sh. Raj Kumar Singh
R/o H. No. L-1-2093,
Gate No. 10 Sangam Vihar,
New Delhi-110062

Sub: - m/o Park Plantation trucks & other equipments in Hort. wing N.A. 12
m/o Park Near Bhargava Village - Narela.
S.M. Ploughing, S.S. good earth, Com, jammans, Soda, Digging holes, P.F. of
Playing Children equipments, Fine dressing etc at site.

Ref. Performance Security/Guarantee Submitted by you vide your letter

No. dt. 1-12-12

Dear Sir (s),


Your quoted/negotiated item rate tender for the above cited work has been accepted on
dt. 23-11-12 behalf of Delhi Development Authority at the rates, terms & condition given below-

1. Estt. Cost. Rs. 851,651=00 (Rs. Eight lac fifty one thousand Six hundred fifty one only)
2. Accepted Amount Rs. 5,45,399=00 (Rs. Five lac forty five thousand three hundred ninety nine only)
3. Time Allowed 50 days

You are requested to attend the office of the undersigned along with a non judicial stamp paper worth Rs. 50/- to complete the formal agreement within 7 days from the date of issue of this letter failing which the award of work shall likely to be withdrawn and the entire amount of your earnest money and performance guarantee shall be forfeited.

It may be noted that if any mistake/error in the nomenclature unit, rates of the item mentioned in the schedule attached occur inadvertently, it will not entitle for payment accordingly. The rates, unit and nomenclature will be taken as per provision of DSR 2007 for the purpose of payment.

You are also requested to contact the A.D. 2/Hort. -X/DDA and start the work at once. please note that the time allowed for carrying out the work as entered in the tender document shall be reckoned from the 10th day after the issue of this letter to commence the work. Your negotiation letter dated shall also form part of the agreement.


**DY. DIRECTOR (HORT.)
HORT. DIVN. NO. X
D.D.A**

Copy To :-

1. Director (H) S.E.Z. /DDA.
2. Commissioner Sales Tax, Work contract cell I.P. Estate, New Delhi.
3. Income Tax Office I.P. Estate, New Delhi.
4. The Labour Commissioner 15 Raj pur Road, Delhi.
5. Dy. Dir. (Hort.) QAC, DDA Vikas Sadan, New Delhi.
6. All Dy. Director/Jt. Dir. (Hort.) DDA
7. Sr. A.O./CAU (NZ)DDA.
8. A.A.O./Hort./DDA.
9. A.D. (H) ² /Hort. -X, he is directed to ensure the quality and quantity of work.
10. H.C. /Hort.- X./DDA
11. O/c


DY. DIRECTOR (HORT.)
HORT. DIVN. NO. X
D.D.A

**DELHI DEVELOPMENT AUTHORITY
HORT. DIVISION -X**

Name of work :- M/o Park Plantation trucks & other equipments in Horticulture Wing N.A. - II
M/o Park Near Bhorgarh Village Narela.

Sub. Head. :- Ploughing, S/S good earth, CDM, Jamuna Sand, Digging Holes, P/F of Playing children equipments, Fine dressing etc. at site.

S.no	DESCRIPTION OF ITEMS	QUANTITY		UNIT	RATE (RS)	AMOUNT (RS)
1	Ploughing the existing ground to a depth of 15 cm to 25 cm and watering the same. All kinds of soil	14528.00	sqm	100/ Sqm.	400 = 00	58112 = 00
2	Supplying and stacking of good earth at site including royalty and carriage with all leads and lifts. (Good earth measured in stacks will be reduced by 20 % for payment)	363.00		Cum.	140 = 00	50820 = 00
3	Supplying and stacking of Cow dung manure at site including royalty and carriage with all leads and lifts (Cow dung manure measured in stacks will be reduced by 8 % for payment)	505.00		Cum.	140 = 00	70700 = 00
4	Supplying and stacking of jamuna sand at site I/C royalty , carriage and loading /un loading for all leads and lifts.	43.00		Cum.	400 = 00	17260 = 00
5	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2: 1 by volume (2 part of stacked volume of earth after reduction by 20 %: 1 part of stacked volume of manure after reduction by 8%) flooding with water dressing including removal of rubbish and surplus earth .if any with all leads and lift (cost of manure. sludge or extra good earth if needed to paid for separately).					
i	SIZE 0.90m. dia and 0.90m. deep	188.00	Nos.	Each	50 = 00	9400 = 00
ii	SIZE 0.60m. dia and 0.60m. deep	883.00	Nos.	Each	20 = 00	17660 = 00
6	Providing and fixing of playing children equipments. [A] Providing And fixing of Bridge ladder as per specification of frame 7'.0' height and 10'.0' long made of 2 ½" dia MS pipe 'A' class of 1" dia MS pipe step bar complete to be fixed in C. cone 1:3:6 (1cement:3C.sand:6graded stone agg. 40mm nominal size) block size 30 X30 X 30cm complete i/c priming and painting as per drawing direction of Eng.-in-charge at site .	2.00	Nos.	Each	10000 = 00	20000 = 00

	[B] Providing and fixing of slide ladder as per specification size -7'.0" x 14'.0" of slope mounted of 40 X 40 X5mm angle iron with 16 SW gauge MS sheet $\frac{3}{4}$ " dia MS pipe railing ladder made of 1" dia MS pipe 'A' class with 1" dia MS pipe duel steps $\frac{3}{4}$ " MS pipe handle and $\frac{3}{4}$ " dia two no stays 4' long complete to be fixed in C.conc 1:3:6 [1Cement :3C.sand : 6 graded stone agg. 40mm nominal size] block size 30 x 30 x 30cm i/c priming and painting as per drawing and directing of Eng.-in-charge at site .	2.00	Nos.	Each	10,000.00	20,000.00
	[C] Providing and fixing of chain swing (double) as per specification of 10"-00" long and 10'-0" height made of 2" dia MS pipe 'A' class with 1" dia MS pipe stays 3'-6" long consisting of 2 No. of chain swing ball bearing type chain 6mm thick with belt type seats. Complete to be fixed in C. cone 1:3:6 [1Cement :3C.sand : 6 graded stone agg. 40mm nominal size] including priming and painting as per drawing and direction of Eng.-in-charge as site.	2.00	Nos.	Each	10,000.00	20,000.00
	[D] Providing and Fixing of Sea Saw as per sepecification of frame made 50mm MS Pipe 'A' class 1.80 mtr.long 0.45 mtr. height with 2 Nos.sea saw flanks made of 30 mm pipe 'A' class,2.43 mtr. long with angle iron 40x40x6mm with 20 mm MS pipe cantilever support handle 16 swg sheet complete to be fixed in C.conc. 1:3:6 [1Cement :3C.sand : 6 graded stone agg. 40mm nominal size] block size 30 x 30 x 30cm i/c priming and painting as per drawing and directing of Eng.-in-charge at site .	2.00	Nos.	Each	7,000.00	14,000.00
7	Preparation of beds for hedging and shrubbery by excavating 60 cm. deep and trenching the excavated base to a further depth of 30cm. refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 Part of stacked volume of earth after reduction by 20 %: one part of stacked volume of sludge or manure after reduction by 8%). Flooding with water filling with earth if necessary. Watering and finally fine dressing, levelling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and levelling as directed within a lead of 50 m lift upto 1.5 m. complete (cost of sludge. Manure or extra earth to be paid for separately).	506.00	Cum.	35.00	17710.00	
8	Fine dressing of the ground.	14528.00	sqm	100/ Sqm.	80.00	11622.00
9	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the good earth shall be paid for separately).	14528.00	sqm	100/ Sqm.	250.00	36320.00

10	Providing and fixing of Precast Concrete Bench [Chair type]with back rest manufactured by using M 30 grade of concrete & reinforced suitable to prevent damage during handling transportation, erection and long use. The bench consists of 2 nos. L-Shape base support in gray cement colour of thickness of 100mm,back height 1000mm.&front height 450mm base width 620mm and 5nos. reinforced concrete planks of in red colour size 1500 x 100 x 50mm and 1no of reinforced concrete planks of size 1500 x 200 x 50 mm. All parts are joined together with galvanized nuts and bolts of suitable size. All bolts are sealed after assembly seating length of the bench 1500mm. Seating height of the bench = 450mm. Total height of the bench = 1000mm. Front face of all planks shall be given special coating to make them water proof and glossy	15.00	Nos.	Each	₹500.00	₹2500.00
11	supply of Plants fully grown free from all disease at site in polythene Bags (size 6"x9")					
i	Tree Plants Ashok Logifolia Ht. 4'-0" - 4'-6" and above	188.00	Nos.	Each	60.00	11280.00
ii	Shrub Plant Calliandra ht. 2'-0" and above	500.00	Nos.	Each	25.00	12500.00
iii	Shrub Plant Ticoma (Gori Chori) ht. 2'-6" and above	383.00	Nos.	Each	25.00	9575.00
iv	Hedge Plants Clerodendrum inerme Ht 2'-0" and above in p/bag at site	2800.0	Nos.	Each	5.00	14000.00
12	supply of Neem oil Cake [in 50 kg. Bagh] at site		14.00	Qtl.	700.00	9800.00
13	Supply of Chemical emulsion in sealed containers including delivery as specified Chlorpyriphos concentrate of 20% EC. at site.		17.00	Ltr.	150.00	2550.00
14	Supply of P, V, C, pipe 3"dia blue colour rain forced, lay flate hose for water delivery W.P. 5 Kg / Cm.2 at site.		360.00	Mtr	80.00	28800.00
15	Supply of Chemical fertilizer at site.					
[A]	Urea [IFFCO / KRIBHCO - Make] at site [in 50 kg packing		5.50	Qtl.	750.00	3850.00
[B]	D.A.P. [IFFCO / KRIBHCO - Make] at site. [in 50 kg packing]		3.50	Qtl.	200.00	700.00
Total					₹. 545399.00	

(Signature)

Dy. Director (Hort.)
Hort. Div. DDA