

DELHI DEVELOPMENT AUTHORITY
HORTICULTURE DIVISION No - X

No. F. 16. (56)/Hort. X/DDA/2012-13/ 4476

Date: - 7-12-12

To,

M/S, Sh. Manoj Kr. Sharma
 109/2, Gali No 5
 Shiv Mandir Road
 Swarnap Nagar, Delhi-42

Sub: - M/o Past irrigation and other
 equipment in front wing (Naza A/c-II)
 M/o Dist. Park (Lala Nala Bagh) Pitambura.
 S.H. S/S good earth, CDM, J. Band, digging holes, S/bonomeal
 P/A Dist. Sir, Removal Malba, Painting etc.

Ref. Performance Security/Guarantee Submitted by you vide your letter

No. dt. 5/12/12

Dear Sir (s),

Your quoted/negotiated item rate tender for the above cited work has been accepted on dt. 23/11/12... behalf of Delhi Development Authority at the rates, terms & condition given below-

1. Estt. Cost. Rs. 373692/- (Three lac seventy three thousand & six hundred ninety two only)
2. Accepted Amount Rs. 401916/- (Four lac one thousand nine hundred & sixteen only)
3. Time Allowed 30 Days

You are requested to attend the office of the undersigned along with a non judicial stamp paper worth Rs. 50/- to complete the formal agreement within 7 days from the date of issue of this letter failing which the award of work shall likely to be withdrawn and the entire amount of your earnest money and performance guarantee shall be forfeited.


It may be noted that if any mistake/error in the nomenclature unit, rates of the item mentioned in the schedule attached occur inadvertently, it will not entitle for payment accordingly. The rates, unit and nomenclature will be taken as per provision of DSR 2007 for the purpose of payment.

You are also requested to contact the A.D. I./Hort. -X/DDA and start the work at once. please not that the time allowed for carrying out the work as entered in the tender document shall be reckoned from the 10th day after the issue of this letter to commence the work. Your negotiation letter dated 13-11-12 shall also form part of the agreement.

Se Grim
DY. DIRECTOR (HORT.)
HORT. DIVN. NO. X
D.D.A

Copy To :-

1. Director (H) S.E.Z. /DDA.
2. Commissioner Sales Tax, Work contract cell I.P. Estate, New Delhi.
3. Income Tax Office I.P. Estate, New Delhi.
4. The Labour Commissioner 15 Raj pur Road, Delhi.
5. Dy. Dir. (Hort.) QAC, DDA Vikas Sadan, New Delhi.
6. All Dy. Director/Jt. Dir. (Hort.) DDA
7. Sr. A.O./CAU (NZ)DDA.
8. A.A.O./Hort./DDA.
9. A.D. (H) I /Hort. -X, he is directed to ensure the quality and quantity of work.
10. H.C. /Hort.-X./DDA
11. O/c.


DY. DIRECTOR (HORT.)
HORT. DIVN. NO. X
D.D.A

**DELHI DEVELOPMENT AUTHORITY
HORT. DIVISION -X**

Name of work :- M/o Park Plantation trucks & other equipments in Horticulture Wing N.A. - II
M/O Distt. Park (Lala wala Bagh) Pitam Pura.

Sub. Head. :- S/S good earth, CDM, Jamuna sand, Digging holes, Supply of bone meal, P/F of Dust bins, Providing and fixing of playing children equipments, Removal malba, painting etc. at site.

S.no	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs)	AMOUNT (Rs)
1	Supplying and stacking of good earth at site including royalty and carriage with all leads and lifts. (Good earth measured in stacks will be reduced by 20 % for payment)	217.00	Cum.	300 -	65100 -
2	Supplying and stacking of Cow dung manure at site including royalty and carriage with all leads and lifts (Cow dung manure measured in stacks will be reduced by 8 % for payment)	244.08	Cum.	210 -	51257 -
3	Supplying and stacking of jamuna sand at site I/C royalty, carriage and loading /un loading for all leads and lifts.	61.60	Cum.	665 -	40964 -
4	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2: 1 by volume (2 part of stacked volume of earth after reduction by 20 %: 1 part of stacked volume of manure after reduction by 8%) flooding with water dressing including removal of rubbish and surplus earth, if any with all leads and lift (cost of manure, sludge or extra good earth if needed to paid for separately).				
5	Supply of bone manure at site. (Packing 40 kg)	250.00	Nos. Each	24 -	6000 -
6	P/F of Dust bins/Litter Bins made of fiber 3mm. Thick average weight 1.35 kg/Sqm of size 430x430x1000mm. Openable at top and having on the support of 40mm. Dia G.I. Pipe 1.30 mtr. long 2 Nos. M.S. hinger of required size to be provided to made it openable and M.S. 16 mm. Square bar 52 cm. long also to be provided and welder with G.I. Pipe in the bottom 2 Nos. M.S. Plate of 100x100x3 mm. thick size to be provided at the bottom of G.I. Pipe 2 Nos. elbows at the top welded with 2 Nos. 16 mm. dia bar 70 mm. long to make it movable position i/c making 5 Nos. holes of 20 mm. diamtr. Bottom of litter bin. Painting G.I. with ready mixed paint of approved brand and colour as per detailed drawing i/e excavation and joined with base in C.C. in the ratio of 1:5:10 (1 cement: 5 C. Sand: 10 graded stone agg. of thickness 10 cms. and top of cement concrete 1:2:4 (1 Cement: 2 C. Sand: 4 graded stone agg. 20 mm. M.S.) as per direction of Officer-in-Charge.	10.00	Nos. Each	1400 -	14000 -

7 Providing and fixing of playing children equipments.				
[A] Providing And fixing of Bridge ladder as per specification of frame 7'.0' height and 10'.0' long made of 2 ½" dia MS pipe 'A' class of 1" dia MS pipe step bar complete to be fixed in C. cone 1:3:6 (1cement:3C.sand:6graded stone agg. 40mm nominal size) block size 30 X30 X 30cm complete i/c priming and painting as per drawing direction of Eng.-in-charge at site.			2.00 Nos. Each	8450- 16900-
[B] Providing and fixing of slide ladder as per specification size -7'.0" x 14'.0" of slope mounted of 40 X 40 X5mm angle iron with 16 SW gauge MS sheet ¾" dia MS pipe railing ladder made of 1" dia MS pipe 'A' class with 1" dia MS pipe duel steps ¾" MS pipe handle and ¾" dia two no stays 4' long complete to be fixed in C.cone 1:3:6 [1Cement :3C.sand : 6 graded stone agg. 40mm nominal size] block size 30 x 30 x 30cm i/c priming and painting as per drawing and directing of Eng.-in-charge at site.			2.00 Nos. Each	8450- 16900-
[C] Providing and fixing of chain swing (double) as per specification of 10"-00" long and 10'-0" height made of 2" dia MS pipe 'A' class with 1" dia MS pipe stays 3'-6" long consisting of 2 No. of chain swing ball bearing type chain 6mm thick with belt type seats. Complete to be fixed in C. cone 1:3:6 [1Cement :3C.sand : 6 graded stone agg. 40mm nominal size] including priming and painting as per drawing and direction of Eng.-in-charge at site.			2.00 Nos. Each	8450- 16900-
[D] Providing and Fixing of Sea Saw as per sepecification of frame made 50mm MS Pipe 'A' class 1.80 mtr.long 0.45 mtr. height with 2 Nos.sea saw flanks made of 30 mm pipe 'A' class, 2.43 mtr. long with angle iron 40x40x6mm with 20 mm MS pipe cantilever support handle 16 swg sheet complete to be fixed in C.conc. 1:3:6 [1Cement :3C.sand : 6 graded stone agg. 40mm nominal size] block size 30 x 30 x 30cm i/c priming and painting as per drawing and directing of Eng.-in-charge at site.			2.00 Nos. Each	4600- 9200-
8 Removal malba / garbage / building rubbish by mechanical transport I/C Carriage, Loading /unloading upto lead 5.00 km., complete as per direction of enginer-in-charge.			80.00 Cum.	80- 6400-
9 Painting with enamel paint of approved brand and manufacture to give an even shade (one or more coat on old steel work),			422.00 Sqm.	35- 147700-
10 supply of Neem oil Cake [in 50 kg. Bagh] at site			26.00 Qtl.	1050- 47300-
11 Supply of Chemical emulsion in sealed containers including delivery as specified Chlorpyriphos concentrate of 20% EC. at site.			61.00 Ltr.	225- 13725-

12	supply of R.H. Pipe double braded I S I. mark I S-444/87 Type-II, Water hose pipe 25 mm, dia working pressure 10.2 kg. F / cm ² , at site.	200.00 Mtr.	1200-	94000-
13	Supply of P, V, C, pipe 3" dia blue colour rain forced, lay flate hose for water delivery W.P. 5 Kg / Cm.2 at sites	120.00 Mtr	80-	96000-
14	Supply of Chemical fertilizer at site.			
[A]	Urea [IFFCO / KRIBHCO - Make] at site [in 50 kg packing	14.00 Qtl.	630-	88200-
[B]	D.A.P. [IFFCO / KRIBHCO - Make] at site. [in 50 kg packing]	8.00 Qtl.	1800-	144000-
Total			₹. 42,916.00	

Dy. Director (Ioc)
Hort Dept. PDA

(Signature)
6/1/12