

To

M/s Fair Deal Creation & Marketing,
A-5,/349, 1st Floor,Paschim Vihar,
New Delhi-110063.

Name of work :M/o Various colonies under Dwarka Zone Nazul A/c-II.
SH :Providing & fixing retro reflective sign boards and guidle maps in
Sec. 7,Dwarka.
Ref: :Letter of intent vide No.F.81 (23)A/cs/WD-8/DDA/2011-12/1580
dt..06.12.2012
Ref of P.G.: :FDR No.462644 A/c No. FD/01/121006045067 dt. 18.12.12 for
Rs. 15,000/-

Dear Sir,

Your item rate e-tender dated 17.10.2012 for the above mentioned work has been
accepted on behalf of DDA at the rates, terms and conditions given below:

1. Estt.Cost. :Rs.2,75,781.00 (Rupees Two lac seventy five thousand
seven hundred eighty one) only
2. Quoted Amount. : Rs.2,84,758.00 (Rupees Two lac eighty four thousand
seven hundred fifty eight) only
3. Accepted Tender : Rs.2,84,758.00 (Rupees Two lac eighty four thousand
seven hundred fifty eight) only
(As per annexure 'A')
4. Percentage for the Purpose : 03.26 % above the Estt Cost based on D.S.2007.
5. Time allowed : 30 Days.

You are requested to attend this office to sign the agreement along with one non-judicial stamp paper worth Rs.50/- (fifty) within 7 days from the date of issue of this letter. Please note that if you fail to sign the agreement within seven days from the date of issue of this letter, of acceptance of the tender is likely to be withdrawn and the earnest money as well as performance guarantee will be forfeited.

You are also requested to contact the A.E. V of this division and start the work at once. Please note that time allowed for carrying out the work as entered in the tender form shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

VAT, Cess ,& other statutory taxes shall be deducted as applicable from time to time.

Encl: Schedule of awarded rates

Yours faithfully


Executive Engineer
Western Division-8

DELHI DEVELOPMENT AUTHORITY

Name of work:-M/o Various colonies under Nazul A/C-II Dwarka zone.
Sub-head:-Providing and Fixing Retro Reflective Sign Boards and Guide Maps in Sector -7, Dwarka.

SCHEDULE OF QUANTITIES
NIT No.:- 19/EE/W/D-8/DDA/2012-13
Estimated Cost: Rs. 2,75,781.00


Handwritten signature

M/s Fair Deal Creation & Marketing

NAME OF THE FIRM

S. No.	Description of item	Qty	Unit	Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. a) All kinds of soil	34.00	Cum	120.00	Rupees One Hundred Twenty Only	4080.00
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	29.00	Cum	30.00	Rupees Thirty Only	870.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	0.80	Cum	2400.00	Rupees Two Thousand Four Hundred Only	1920.00
4	Centering and shuttering including strutting, propping etc. and removal of form work for : a) Foundations, footings, bases for columns	16.00	sqm	180.00	Rupees One Hundred Eighty Only	2880.00
5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : a) 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	4.00	Cum	4500.00	Rupees Four Thousand Five Hundred Only	18000.00
6	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. a) Thermo-Mechanically Treated bars	4.00	kg	62.00	Rupees Sixty Two Only	248.00
7	Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer welded and bolted including special shaped a) Hot finished seamless type tubes	1561.00	kg	80.00	Rupees Eighty Only	124880.00

9	<p>steel work riveted, bolted or welded in built up sections, trusses and framed including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete</p> <p>Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : a) Two or more coats on new work</p>	352.00	kg	70.00	Rupees Seventy Only	24640.00
10	<p>Manufacturing supplying and fixing retro reflective overhead signage boards made up of 2mm thick aluminium sheet face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge. (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment). 16.60.1 Overhead informatory road signage.</p>	18.00	sqm	3000.00	Rupees Three Thousand Only	54000.00
11	<p>Providing Retro-reflective regulatory sign board of size 900mm dia meter made out of 2mm thick aluminium sheet, face to be fully covered with high intensity encapsulated lens type retro -reflective sheeting as approved by Engineer-in-charge. Letter, symbols, borders etc. will be as per IRC - 67 with required colour scheme on the boards and with the high intensity grade A. The aluminium sheet to be riveted to M.S. frame of angle iron of size 40x40x4mm. The boards will be fixed to 1 No. 50x50mm square post made of M.S. angle 50x50x4mm, 4m long welded to the frame with adequate anti-theft arrangement. Sheet work to be painted with two or more coats of synthetic enamel paint over an under coat (primer) and back side of aluminium sheet to be painted with two or more coats of epoxy paint including appropriate priming coat complete in all respects as per direction of Engineer-in-charge</p>	10.00	sqm	5000.00	Rupees Five Thousand Only	50000.00
TOTAL						


 Executive Engineer
 Western Division-8
 D.D.A.