

**OFFICE OF THE EXECUTIVE ENGINEER
SOUTH EASTERN DIVISION No.11 DDA
VIKAS SADAN NEW DELHI**

NOTICE INVITING TENDER

Sealed **Item Rate** tender are invited for the following works on behalf of the DDA from the approved and eligible contractors of appropriate class of DDA, up to 3.00 PM on the date of opening (mentioned below), which shall be opened on the same day at 3.30 PM at 1st Floor, Press Building, Vikas Sadan, INA, New Delhi-23 by the Executive Engineer/SED-11/DDA in the presence of the contractors or their authorized representatives. Tender documents can be had on any working day from the date of circulation between 11.00AM to 3.00PM on payment of the cost of tender + D Vat (non-refundable) mentioned against each work, on production of valid enlistment certificate, certificate of registration with Sale Tax Deptt. of the GNCTD from CAU/SZ/DDA/ Shahpur Jat, New Delhi and Centralized Tender Office at Vikas Sadan, INA, New Delhi-23. The sale of tender will be stopped four days before the date of opening (including the date of opening).

The contractors can submit their tender in sealed envelope only up to seven days before the date of opening between 10.00AM to 5.00 PM except the date of opening when it will be up to 3.00PM. The tender can also be sent by the contractors through Registered Post, which should reach the Office of the EE/SED-11/DDA at least one day before the last date of the receipt of tenders.

The manner of submission of tender, opening of the same and entry of contractors/their representatives to the place of opening shall be as provided in clause-3(a) (b) and (c) of the PWD-6 forming part of tender documents.

The Earnest Money shall accompany the tender in the form of Call at Deposit Receipt or Demand Draft of a scheduled Bank guaranteed by the Reserve Bank of India in favour of Sr. AO/CAU/SZ/DDA. The tender of the contractor who does not enclose the earnest money in prescribed manner shall be summarily rejected.

NIT No.	Name of Work & Sub-head	Estimated Cost Earnest Money	Cost of Tender Time Allowed	Last dt. of Sale Dt. of opening
---------	-------------------------	---------------------------------	--------------------------------	------------------------------------

1. NIT.No. 58/EE/SED-11/DDA/10-11

M/O scheme under N/A-II (South Zone)

SH: Repair of rain shelter at Lala Lajpat Memorial park at Lajpat Nagar.

Rs. 1,62,763/-	Rs. 500/- + Vat	10.12.10
Rs. 3,255/-	2 (Two) Months	15.12.10

2. -DO-1 NIT No. 59/EE/SED-11/DDA/10-11

SH: Repairing of Boundary wall, Gate & Grill etc. at Lala Lajpat Rai Memorial park at Lajpat Nagar.

Rs. 2,12,947/-	Rs. 500/- + Vat	10.12.10
Rs. 4,259/-	2 (Two) Months	15.12.10

30/11/10
EXECUTIVE ENGINEER
SED-11/DDA

P.T.O

SCHEDULE OF QUANTITIES

Name of work : M/O scheme under Nazul Account-II/South Zone.
Sub-Head : Repair of Rain Shelter at Lala Lajpat Memorial Park at Lajpat Nagar.

ESSH Contd to 16274
E.M. Rs. 325
T. Ahmed - 2 (74)

Sl.No.	Description of item.	Qty.	Unit.	Rate.	Amount.
1.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	114.00	Sqm.		
2.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade; a) Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. b) One or more coat on old work.	120.00 67.00	Sqm. Sqm.		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering-all work upto plinth level; a) 1:3:6(1 cement:3 coarse sand:6 graded stone agg. 20mm nominal size).	17.00	Cum.		
4.	Welding by Gas or electric plant including transportation of plant at site etc. complete.	144.00	QM		
5.	Steel work welded in built up sections/framed work including cutting, riveting, fitting in position and applying a priming coat of approved steel primer using structural steel etc. as required; a) In gratings, frames, guard bar, ladder, railings, brackets gates and similar works.	106.00	Kg.		
6.	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4(1 cement:4 coarse sand); a) 25 mm thick.	114.00	Sqm.		

nota stone slabs 25mm thick in risers of steps, skirting, dado and pillars laid on 12mm (average) thick cement mortar 1:3 (1 cement:3 coarse sand) and jointed with grey cement slurry mixed with rubbing and polishing complete.

9.00

Sqm.

Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction and of approved size and design/shape laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with coarse sand etc. all complete as per the direction of Engineer-in-charge.

35.00

Sqm.

Supplied Material:-

1. Cement 6.70 M.T @ Rs 400/- P.M.T shall be
issued from any DDA store at Delhi/New Delhi.

SCHEDULE OF QUANTITY

ESTH. Cost Rs. 212944-
E.M. Rs. 4259-
T. Allowed = 2 (Two) Months

NAME OF WORK ;

M/o Various colonies under South Zone.

SUB-HEAD:

Repairing of boundary wall, Gate & Grill etc. at Lala Laipat Rai Park at Laipat Nagar.

Memorial

Sl. No.	Description of Item	Qty.	Unit	Rate (Rs.)	Amount
1.	Earth work in ourface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth up to 50m and lift up to 1.5m, disposed soil to be leveled and neatly dressed: a) All kinds of soil.				
		4.00	Cum.		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: a) 1:5:10 (11 cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size).	1.00	Cum.		
3.	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: a) Cement mortar 1:6 (1 cement: 6 coarse sand).	10.00	Cum.		
4.	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and size in: a) Cement mortar 1:6 (1 cement : 6 coarse sand).	40.00	Cum.		

5.	Providing and laying damp-proof course 40mm thick with cement concrete 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 12.5 mm nominal size.	2.00	Sqm.		
6.	12 mm cement plaster of mix. a) 1:6 (1 cement: 6 fine sand).	342.00	Sqm.		
7.	Steel work welded in built up sections/framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required:				
8.	a) In gratings, frames, guard bar, ladder, failings, brackets gates and similar works. Steel work in built up tubular trusses including cutting, hoisting fixing in position and applying a priming coat of approved steel primer, welded and bolted including special shaped washers etc. complete. a) Hot finished welded type tubes.	476.00 722.00	Kg. Kg.		

Stipulated Material:-

1. Cement - 4.5 m.T @ Rs 4600 / m.T shall be
issued from DDA Store at Delhi / New Delhi.