

DELHI DEVELOPMENT AUTHORITY
SOUTH EASTERN DIVISION NO. XI

NOTICE INVITING TENDER

Sealed item rate tender are invited for the following works by the Executive Engineer/SED- XI, Vikas Sadan, INA upto 3.00 PM on behalf of DDA from the approved contractors of appropriate class of DDA, CPWD, MBS, P&T & Railway on the dates mentioned below which shall be opened on the same day at 3.30 P.M at Vikas Sadan (Press Building) near INA Market, New Delhi in the presence of intending purchase of their authorized representatives.

The tender documents can be obtained on any working day from the CAU (SEZ) Sale counter, Press Building, Vikas Sadan between 11.00 AM to 3.00 PM on payment of cost of tenders (non-refundable) as well as amount of Earnest Money mentioned against each work on production of valid Enlistment Certificate and valid certificate of Registration with work contract cell of Sale Tax Deptt of GNCTD & Tax clearance certificate issued by the Work Contract Cell. Sale of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender documents.

The earnest money should accompany the tender application in the form of a Call deposit receipt or demand draft of a Schedule Bank guaranteed by the Reserve Bank of India in favour of A.O (CAU)-SEZ/DDA.

S.No. NIT No. Name of work	Estt. cost	Last dt. of Sale
	Earnest Money Cost of tender	Dt. of Opening Time allowed

1. NIT.No.1/EE/SED-11/DDA/08-09

M/O Lala Lajpat Rai Memorial Park at Lajpat Nagar.
SH: Construction of pedestrian & Plat-form for Bust
of Lala Lajpat Rai.

Rs. 1, 34, 034/-	17.4.08
Rs. 2, 681/-	22.4.08
Rs. 500/-	1 (One) month.

2. NIT.No.2/EE/SED-11/DDA/08-09

- DO -

SH: Repair of brick masonry chamber and extending of water line.

Rs. 1, 95, 757/-	17.4.08
Rs. 3, 915/-	22.4.08
Rs. 500/-	45 days

No. F-5(1 & 2) SED- XI/DDA/A/33-08/383

Dt. 11/4/08

EXECUTIVE ENGINEER/SED- XI

Cent. 2/-

Copy to:

1. CE(SEZ) DDA 2. SE, CC-16 3. Director (System) DDA for placing it in Web site of DDA 4. FO to CE(SEZ) 5. PAO(EW) DDA 6. AO(W) I 7. DDA Contr. Association (Regd) 40-A Vikas Minar 8. In. Tax Officer Contr. Circle ITO 9. Contr. Association, CPWD Y-Shape Bldg. 10. Contr. Welfare Association (Regd) 12. A Barrack No.1 Bk A Vikas Kuteer 11. Labour Commissioner, Rajpura Road 12. All EEs/ DDA. 13. EE/WD-12 14. All AEs/SED-XI 15. Chief Security Officer/ DDA 16. HC/SED-XI 17. Tender clerk, Centralised Tender Office, Vikas Sadan 18. Delhi Contr. Welfare Association, 2613, Gali Dharamshala Wali, Kali Masjid, Rukman Gate. 19. AO CAU (SEZ), Shahpurjat, 20 Delhi Contr. & Builder Association, H.NO. 5508, Ch. Prem Singh Bhawan, New Chandrawal, Ch. Bhim Singh Road 21. Trans Yamuna DDA Contr. Association (Regd) Gandhi Nagar. 22. Dy. Commissioner (Work Contract) Bikri Kar Bhawan I.P. Estate 23. Notice Board of SED-XI 23. Cashier/SED-XI/DDA 25. Delhi Govt. Contractors Welfare Assn (Regd) 174, Trivent Apprtt near Police Stn. Vivek Vihar Delhi-110095. 26. DDA web site dda tender @dda.org.in & Dir system dirsystem@dda.org.in.

Galaxy 11/4/08
EXECUTIVE ENGINEER/SED-XI
11/4/08
11/4

17.4.08	17.4.08
22.4.08	22.4.08
42 days	300/-

SCHEDULE OF QUANTITY
NAME OF THE WORK : M/o LALA LAJPAT RAI MEMORIAL PARK AT LAJPAT NAGAR.
SH : Construction of Pedestrial & Platform for bust of Lala Lajpat Rai.

S.No.	Description of items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1.	Earth work in excavation by mechanical means (Hydraulic Excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm. on plan) including dressing of sides and ramming of bottoms, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	(a) All kinds of soil	26.00	Cum		
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:				
	(a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	11.00	Cum		
	(b) 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	1.00	Cum		

Estt. Cost Rs 134,034 -
 E. Money Rs 2681 -
 T. Allowed - One Month.

3.	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in : (a) Cement mortar 1:6 (1 cement : 6 coarse sand)	26.00	Cum		
4.	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	54.00	Kg.		
5.	Extra for providing pipe in place of section etc.	54.00	Kg.		
6.	12mm Cement Plaster of mix : 1:4 (1 cement : 4 c. sand)	6.00	Sqm.		
7.	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand): (a) 25mm thick	60.00	Sqm.		
8.	40mm thick rubbed stone flooring over 20 mm(average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand) with joints 3mm thick, side buttered with cement mortar 1:2 (1 cement : 2 stone dust) admixed with pigment to match the shade of stone and pointing with same mortar).				
	(a) Red sand stone	18.00	Sqm.		

NOTE :- Cement 4.50 M.T @ Rs. 4600 = 00 Per M.T shall be issued from any D.D.A store Delhi | New Delhi.

Schedule of Quality

NAME OF WORK:- M/o Lala Lajpat Rai Memorial Park at Lajpat Nagar.

Sh:- Repairing of Brick Masoning Chamber and extending of water line.

ESSH. Cost Rs 1,95,757-
E.Money Rs 13915-
Time Allowed - 45 days.

SL.NO.	NAME OF WORK	QTY.	UNIT	RATE	AMOUNT
1.	Earth work in excavation by mechanical means (hydraulic excavator) & manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 Sqm on plan) including disposal of excavated earth, lead upto 50 m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.				
	(a) All kinds of soil.	78.00	Cum		
2.	Excavating trenches of required width for pipes,cables etc.including excavation of sockets,and dressing of sides,ramming of bottoms,depth upto 1.5m including getting out the excavated soil and then returning the soil as required,in layers not exceeding 20cm in depth including consolidating each deposited layer by ramming,watering,etc.and disposing of surplus excavated soil as directed,within a lead of 50m: (All kind of Soil)				
	(a) Pipes,cables etc.not exceeding 80mm dia.	250.00	Metre		

SL.NO.	NAME OF WORK	QTY.	UNIT
3.	Providing and fixing G.I pipes complete with G.I fittings including trenching and refilling etc. (<i>External work</i>) (a) 50mm dia. nominal bore (b) 32mm dia. nominal bore	250.00 40.00	metre metre
4.	Providing and fixing of soil closing valve I/C fixing Nipple of 32mm dia of required length over 15mm length and suitable for hydrant of 32mm dia.	40.00	Each
5.	Providing and fixing G.I Union in existing G.I pipe line, cutting and threading the pipe and making long screws including excavation refilling the earth or cutting of wall and making good the same complete wherever required. (a) 50mm nominal bore.	<i>two Coats</i> 12Nos.	Each
6.	Painting G.I pipes and fittings with <i>anti-Corrosive</i> Bitumic paints of approved quality. (a) 50mm diameter of pipe (b) 32mm diameter of pipe	250.00 40.00	Metre Metre

:: 3 ::

SL.NO.	NAME OF WORK	QTY.	UNIT
7.	Providing and filling sand of grading zone V or coarser grade all-round the G.I.pipes in external work. (a) 50mm diameter pipe	250.00	Metre
8.	Providing and fixing gun metal gate valve with C.I.wheel of approved quality (screwed end): (a) 50mm nominal bore.	4Nos.	Each
9.	Making connection of G.I distribution branch with G.I main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete. (a) 50 to 80mm nominal bore.	7Nos.	Each
10	Providing and fixing Gun metal non-return valve of Approved Quality (Screwed end) 50mm nominal Bore (a) Vertical	1 No	Each

SL.NO.	NAME OF WORK	QTY.	UNIT
11.)	Constructing masonry Chamber 90x90x100 cm, inside with 75 class designation brick work in cement mortar 1:4 (1 cement: 4 coarse sand) for sluice valve, with C.I. surface box 100 mm top diameter, 160mm bottom diameter and 180 mm deep (inside) with chained 1ld and RCC to slab 1:2:4 mix (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement:5 fine sand: 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement: 3 coarse sand) 12mm thick finished with a floating coat of neat cement complete as per standard design.	2Nos.	EACH
	(CQ) WITH F.P.S. BRICKS		

NOTE:- Cement 0.50 M.T @ Rs. 4600/- per M.T
 shall be issued from any D.D.A. Store
 Delhi / New Delhi.