

**DELHI DEVELOPMENT AUTHORITY
SOUTH EASTERN DIVISION NO.XI**

NOTICE INVITING TENDER

Scaled item rate tender are invited for the following works by the Executive Engineer/SED.XI, Vikas Sadan, INA upto 3.00 PM on behalf of DDA from the approved contractors of appropriate class of DDA, ~~DDA, SED, EE, B&T & P&S~~ on the dates mentioned below which shall be opened on the same day at 3.30 PM at Vikas Sadan (Press Building) near INA Market, New Delhi in the presence of intending purchaser or their authorized representatives.

The tender documents can be obtained on any working day from the CAU(SEZ)/ Sale counter, Press Building, Vikas Sadan between 11.00 AM to 3.00 PM on payment of cost of tenders (non-refundable) as well as amount of Earnest Money mentioned against each work on production of valid Enlistment Certificate and valid certificate of Registration with work contract cell of Sale Tax Deptt. of GNCTD & Tax clearance certificate issued by the Work Contract Cell. Sale of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender documents.

The earnest money should accompany the tender application in the form of a Call deposit receipt or demand draft of a Scheduled Bank guaranteed by the Reserved Bank of India in favour of A.O.(CAU)SEZ/DDA.

S.No. NIT NO. Name of work	Estt. Cost	Last dt. Of Sale
	Earnest Money	Di. Of opening
	Cost of Tender	Time allowed

1. NIT.No.7/EE/SED-11/DDA/08-09
D/O lala Lajpat Rai memorial park at Lajpat Nagar.
SH: Repair of store room & toe wall near Play area.

Rs. 1,97,116/- ✓	2.5.08 ✓
Rs. 3,942/- ✓	6.5.08 ✓
Rs. 500/- ✓	45 days ✓
2. NIT.No.8/EE/SED-11/DDA/08-09
- DO -
SH: Repair of Entrance & paths in side the park.

Rs. 1,79,627/- ✓	2.5.08 ✓
Rs. 3,593/- ✓	6.5.08 ✓
Rs. 500/- ✓	45 days ✓
3. NIT.No.9/EE/SED-11/DDA/08-09
M/O completed scheme finishing & furnishing i/c T.C. etc. complete at Vikas Sadan.
SH: Replacement of damaged/old tile flooring and pannelling etc. at EM's Sectriate at B-Block, Ist floor Vikas Sadan.

Rs. 1,92,269/- ✓	2.5.08 ✓
Rs. 3,845/- ✓	6.5.08 ✓
Rs. 500/- ✓	15 days ✓
4. NIT.No.10/EE/SED-11/DDA/08-09
- DO -
SH: P/F false ceiling in the office of EM's Secretriatic at B-Block, Ist floor.

Rs. 1,84,151/- ✓	2.5.08 ✓
Rs. 3,683/- ✓	6.5.08 ✓
Rs. 500/- ✓	15 days ✓

Conditions for the work at Sl.No.4

1. Tenders will be issued to those agencies who have executed atleast two works of similar nature during the last five years costing not less than 50% of the estimated cost put to the tenders.
2. Tenders will be issued from division office i.e. EE/SED-11/DDA Vikas Sadan, INA, New Delhi.

24/4/08
Executive Engineer
SED - 11 : DDA

Dt: 24/4/08

Copy to: 1. CE(SEZ) 2. SE/CC-16 3. Director(System)DDA for placing it in Web site of DDA. 4. FO to CE(SEZ) 5. PAO(EW)DDA 6. AO(W)I, 7. DDA Contr. Association (Regd.) 40-A, Vikas Minar 8. In. Tax Officer Contr. Circle ITO, 9. Contr. Association, CPWD Y-Shape Bldg. 10. Contr. Welfare Association (Regd.) 12-A, Barrack No. 1, Blk. A, Vikas Kuteer, 11. Labour Commissioner, Rajpura Road, 12. All Ees/DDA, 13. EE/WD.12 14. All AEs/SED.XI, 15. Chief Security Officer/DDA, 16. HC/SED.XI, 17. Tender Clerk, Centralised Tender Office, Vikas Sadan, 18. Delhi Contr. Welfare Association, 2613, Gali Dharamshala Wali, Kali Masjid, Turkman Gate, 19. AO/CAU(SEZ), Shahpurjat, 20. Delhi Contr. & Builder Association, H.No.5508, Ch. Prem Singh Bhawan, New Chandrawal, Ch. Bhim Singh Road, 21. Trans Yamuna DDA Contr. Association (Regd.) Gandhi Nagar, 22. Dy. Commissioner (Work Contract) Bikri Kar Bhawan, I.P.Estate, 23. Notice Board of SED.XI, 24. Cashier/SED.XI/DDA, 25. Delhi Contr. Welfare Assn (Regd.), 179, Tisvoni Appa near Police Stn, Vivek Vihar Delhi-45.
26. DDA Web site dda tender @dda.org.in & Dir system@dda.org.in.

Executive Engineer
SED - 11 : DDA

24/4/18

24/4/18

SCHEDULE OF QUANTITIES

Name of Work: M/o LALA LAJPAT RAI MEORIAL PARK AT LAJPAT NAGAR

SH: Repair of Store Room and Toe wall near play area

S.No	Description of Items	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (Not exceeding 1.5m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m a) All kinds of soil	26.00	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level: a) 1:5:10 (1 cement : 5 coarse sand: 10 graded stone aggregate 40mm nominal size)	6.00	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level: a) 1:2:4 (1 cement : 2 Coarse sand : 4 graded stone aggregate 20mm nominal size)	1.15	Cum		
4	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement: 4 coarse sand): 25mm thick.	55.62	Sqm		

Estt: Cost Rs 1,97,116 -
E.M, Rs 3942 -
T-Allowed - 45 days?

S.No	Description of Items	Rate (Rs)	Amount (Rs)	Qty	Unit	Rate (Rs)	Amount (Rs)
5	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.			26.82	Sqm		
6	Carriage of material by Mechanical Transport i/c loading, unloading and stacking complete for all lead & lift a)lime moorum, building rubbish			8.00	Cum		
7	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: a) Cement mortar 1:6 (1 cement:6 coarse sand)			27.87	Cum		
8	12mm cement plaster of mix 1:6 (1 cement : 6 coarse sand)			51.00	Sqm		
9	15mm cement plaster of mix 1:6 (1 cement: 6 coarse sand) on the rough side of single or Half brick wall.			62.65	Sqm		
10	Demolishing Brick work manually / by Mechanical means i/c stacking of serviceable material and disposal of unserviceable material within 50m lead as per direction of Engineer-in-Charge in cement Mortar.			10.00	Cum		
11	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50m (stacks of cleaned bricks shall be measured): Brick work in cement mortar			2000.00	1000 Nos		

S.No	Description of Items	Qty	Unit	Rate (Rs)	Amount (Rs)
12	6mm cement plaster of mix: 1:3 (cement : 3 fine sand)	28.80	Sqm		
13	Colour washing such as green, blue or buff to give even shade: a) New work (two or more coats) with a base coat of white washing with lime	79.80	Sqm		
14	Finishing walls with water proofing cement paint of required shade: a) New work (Two or more coats applied @ 3.84 kg/10Sqm) b)	62.65	Sqm		
15	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15 landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size).	4.03	Cum		
16	Centering and shuttering including strutting, propping etc and removal of form for: a) Suspended floors, roofs, landings, balconies and access platform. b) Lintels, beams, plinth brams, girders, bressumers and centilevers	31.19 2.26.	Sqm Sqm		

S.No	Description of Items	Rate (Rs)	Amount (Rs)	Qty	Unit	Rate (Rs)	Amount (Rs)
17	Reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete. (Cold twisted bars or thermo mechanically treated bars)			604.00	Kg		
18	Steel work welded in build up section / framed work i/c cutting, hoisting, fixing in position and applying a priming coat of approved Steel primer using Structural steel etc as required. (in grating frames, guard bar, ladder, railing, Brackets, gates and similar works)			245.00	Kg		

Rs-600/- per M.T. **NOTE:-i) Cement: 5.68 M.T. @ Rs4600/- per M.T. shall be issued from any DDA Store Delhi/New Delhi**
 (Rs) 0.6 M.T. @ Rs 35,493.00 per ii) **Steel :** (T.M.T. Bars) 0.6M.T. @ Rs 35,493.00 per M.T. shall be issued from any DDA Store Delhi/New Delhi

SCHEDULE OF QUANTITIES

SCHEDULE OF QUANTITIES

Name of Work: D/O LALA LAJPAT RAI MEORIAL PARK AT LAJPAT NAGAR
SH: Repair of Entrance & Path Inside the park

S.No.	Description of Items	Unit	Rate (Rs)	Amount (Rs)	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (Not exceeding 1.5m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m	Cum			30.00	Cum		
2	Providing and laying in position concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level: a) 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40mm nominal size)	Cum			4.12	Cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level: a) 1:2:4 (1 cement : 2 Coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum			4.58	Cum		
4	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 1 cement: 4 coarse sand): a) 25mm thick.	Sqm			124.00	Sqm		

Estt. cost Rs 1,79,627 -
Sim. Rs 3593 -
J. Allowed - 45 days

5	Carriage of material, lime, moorum, building rubbish by Mechanical Transport l/c loading unloading and stacking complete for all lead & lift as per direction of Engineer-in-Charge	19.00	Cum		
6	Brick work with F.P.S bricks of class designation 75 in foundation and plinth in: a) Cement mortar 1:6 (1 cement: 6 coarse sand)	8.25	Cum		
7	12mm cement plaster 1:2 (1 cement: 2 stone dust)	123.00	Sqm		
8	Dismantling old plaster or skirting racking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 mtrs lead	108.66	Sqm		
9	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement in position to the required line, level and Curvature joints with cement mortar 1:3 (1 cement : 3 coarse sand) including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm) including making drainage opening wherever required complete etc as per direction of Engineer-in-Charge (Length of finished Kerb edging shall be measured for payment) Pre cast C.C.Kerb stone shall be approved by Engineer-In-Charge.	7.94	Cum		

NOTE:- Cement 5:27:MT @ Rs 4600/- per M.T. shall be issued from any DDA store Delhi/ New Delhi.

SCHEDULE OF QUANTITIES

Name of Work: M/o COMPLETED SCHEME FINISHING AND FURNISHING I/C T.C. etc. COMPLETE AT VIKAS SADAN.

SH: Replacement of Damaged/Old tile flooring and panneling etc at EM/S Sect. etc at B-Block 1st Floor

S.No.	Description of Items	Qty	Unit	Rate(Rs)	Amount(Rs)
1	Providing and laying polished vitrified floors tiles in different sizes (thickness to be specified by the manufacturer) with water absorptions less than 0.08% and confirming to IS-15622 & approved make in all colours and shades laid in 20mm thick cement mortar 1:4 (1 cement: 4 C/sand) i/c grouting the joints with white cement matching pigment etc complete a) size of tile 60x60 cum	80.00	Sqm		
2	P/Fixing paneling or paneling and glazed in panelled or panelled and glazed shutters for Doors, Windows and clearstory windows. (Area of opening for panel inserts excluding portion inside grooves or rabates to be measured) paneling for panelled or panelled and glazed shutters 25mm to 40mm thick. Plywood 7 ply, 9mm thick a) Decorative plywood one side decorative veneer and commercial veneer on other face (Type-I)conforming to IS 1328 BWR type	63.00	Sqm		

Esst. Cost Rs 192269-
E.M. Rs 3845-
T.Allowance - 15 days

3	Providing wood work, inframes of doors, windows, clearstory window and other frames, wrought framed and fixed in position. a) Klin seasoned and chemically treated Hollock wood	0.20	Cum		
4	P/Fixing wooden moulded beading to door and window frames with iron screws, plugs, and priming coat on unexpected surface etc complete a) Hollock wood size 50 x 12mm	220.00	Mts		

NOTE :- CEMENT 1.00 M.T @ Rs. 4600/- per M.T
shall be issued from any D.D.A Store
Delhi | New Delhi.

SCHEDULE OF QUANTITIES

Estt. Cost Rs 1,84,151/-
E.M. Rs 3683 -
T. Allowed - 15 days

Name of Work: M/o COMPLETED SCHEME FINISHING AND FURNISHING I/C T.C. etc. COMPLETE AT VIKAS SADAN.

SH: P/F False Ceiling in the office of E.M.'s Secretariat at 'B' Block Ist floor.

S.N	Description of Items	Qty	Unit	Rate(Rs)	Amount(Rs)
1	Providing & Fixing of Luxalon or equivalent Aluminium Clip in Tile ceiling system comprising of Tile of 600 mm wide and 600 mm long manufactured of 0.7mm Aluminium perforated 1.5mm dia holes in a 3 mm diagonal square pattern giving a 22% open area. The Tile will be manufactured on advanced equipment which includes several leveling stages in the manufacturing process. Two sides of each tile will be raised and piped and stopped to ensure positive engagement into the spring tee yet allow for demounting of individual tiles. All tiles will be beveled edged. The execution facilitates easy access without having to remove the tiles from the suspension system. The tiles will remain clipped to the suspension profiles. The tiles shall be stove enameled coil coated made out of aluminium alloy 3105 for higher strength. The tiles shall be clipped into clip in profile of 0.5 mm thick G.I. The clip in profile shall be supported from slab by means of nonius hangers fixed to the upper structure at a maximum distance of 1250mm centre to centre. Primary suspension profiles will be fixed at both ends to prevent upward movement. Secondary suspension profiles will be fastened to the primary suspension by means of rail connectors to support the tiles. The ceiling perforated tile / planks shall be provided with factory fitted non-woven acoustic textile of Freudenberg, with an NRC value of 0.70 all complete as per direction of Engineer-in-Charge.	52.00	Sqm		