

**DELHI DEVELOPMENT AUTHORITY
SOUTH EASTERN DIVISION NO.XI**

NOTICE INVITING TENDER

Sealed item rate tender are invited for the following works by the Executive Engineer/SED.XI, Vikas Sadan, INA upto 3.00 PM on behalf of DDA from the approved contractors of appropriate class of DDA, CPWD, MES, P&T & Railway on the dates mentioned below which shall be opened on the same day at 3.30 PM at Vikas Sadan (Press Building) near INA Market, New Delhi in the presence of intending purchaser or their authorized representatives.

The tender documents can be obtained on any working day from the CAU(SEZ)/ Sale counter, Press Building, Vikas Sadan between 11.00 AM to 3.00 PM on payment of cost of tenders (non-refundable) as well as amount of Earnest Money mentioned against each work on production of valid Enlistment Certificate and valid certificate of Registration with work contract cell of Sale Tax Deptt. of GNCTD & Tax clearance certificate issued by the Work Contract Cell. Sale of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender documents.

The earnest money should accompany the tender application in the form of a Call deposit receipt or demand draft of a Scheduled Bank guaranteed by the Reserved Bank of India in favour of: A.O.(CAU)SEZ/DDA.

S.No. NIT NO. Name of work	Estt. Cost Earnest Money Cost of Tender	Last dt. Of Sale Dt. Of opening Time allowed
----------------------------	---	--

1. NIT.No.52/EE/SED-XI/DDA/07-08

M/O completed scheme finishing & furnishing i/c T.C.etc.complete at Vikas Sadan.
SH :- P/L laminate flooring in the office of principle Counr.-
Cum-Sectrary at B-Block, IVth floor.

Rs.1,09,488/-	25.1.08
Rs. 2,190/-	29.1.08
Rs. 500/-	15 days

2. NIT.No.53/EE/SED-XI/DDA/07-08

- BO -

SH: Repair & refixing of missing /fallen down Bhelpur tiles on facia at Vikas Sadan.

Rs.1,93,580/-	-BO-
Rs. 3,872/-	-BO-
Rs. 500/-	2 Months.

No:F.5(497,498)/SED.XI/DDA/A/07-08/ 972

Executive Engineer/SED.XI

Dt. 16/1/08

Copy to: 1. CE(SEZ) 2. SE/CC-16 3. Director(System)DDA for placing it in Web site of DDA. 4. FO to CE(SEZ) 5. PAO(EW)DDA 6. AO(W)I. 7. DDA Contr. Association (Regd.) 40-A, Vikas Minar 8. In. Tax Officer Contr. Circle ITO, 9. Contr. Association, CPWD Y-Shape Bldg. 10. Contr. Welfare Association (Regd.) 12-A, Barrack No. 1, Blk. A, Vikas Kuteer. 11. Labour Commissioner, Rajpura Road, 12. All Ees/DDA, 13. EE/ WD.12 14. All AEs/SED.XI, 15. Chief Security Officer/DDA. 16. HC/SED.XI, 17. Tender Clerk, Centralised Tender Office, Vikas Sadan, 18. Delhi Contr. Welfare Association, 2613, Gali Dharamshala Wali, Kali Masjid, Turkman Gate, 19. AO/CAU(SEZ), Shahpurjat, 20. Delhi Contr. & Builder Association, H.No.5508, Ch. Prem Singh Bhawan, New Chandrawal, Ch. Bhim Singh Road, 21. Trans Yamuna DDA Contr. Association (Regd.) Gandhi Nagar, 22. Dy. Commissioner (Work Contract) Bikri Kar Bhawan, I P Estate, 23. Notice Board of SED.XI, 24. Cashier/SED.XI/DDA, 25. Delhi Govt. Contractors Welfare Assn(Kgd.) 179, Triveni Appt. near Police Stn, Virek Vihar, Delhi-110095.
26. DDA web site ddatender@dda.org.in & Mr. System → dirsystem@dda.org.in

Executive Engineer

16/1/08 16/01/08

ESST. Cost Rs 1.09, 488/-

SCHEDULE OF QUANTITY

Name of work:- ^{M^b}Completed Scheme finishing and furnishing i/c T.C etc complete at Vikas Sadan.
SH. :- P/L Laminate flooring in the office of Priciple comm&cum-Sectratry at 'B' Block, 4th Floor.

S.No.	Description of item.	Qty.	Unit.	Rate	Amount.
1.	Providing and laying 8mm thick laminate Pergo, krone, decelive or equivalent floor with 0.2mm thick direct laminate on top developed core plank of size 1285mm x 195 ^{mm} having tongue and grooved laid as per the manufacture guide lines, before laying the material should be got approval by the Engineer-in-charge.	60.48	m ² Sqm.		
2.	P/Fixing four in one beading at entrance complete as per the direction of Engineer-in-charge.	3.00	Mts.		
3.	P/Fixing beading around the periphery of the flooring before fixing the material should be got approval from the competent authority as per direction of engineer-in-charge.	31.20	Mts.		

SCHEDULE OF QUANTITY

Estt. Cost Rs 193580/-

Name of work:-

M/O COMPLETED SCHEME FINISHING & FURNISHING I/C FCC ETC. COMPLETE AT VIKAS SADAN

SH: Repair & Refining of missing / fallen down Dholpur tiles on fascia at Vikas Sadan.

S.No.	Description of Items	Qty	Unit	Rate(Rs)	Amount(Rs)
1	P/Fixing Dholpur stone tiles of 10mm Av. thickness of required size but not exceeding 20x7.5cm on external surface bends, fascia and on circulation portions etc, the tile should be fixed suitable polymer adhesive of approved brand and manufacture i/c preparing the surface properly by chisel -ing to bring the tile in level with existing tile joint of tile should match with the colour of tile i/c the cost of jhoola and other safety arrangement all complete as per the direction of Engineer-in-charge.	1700 Nos	EACH		
	a) upto floor two level				
	b) From floor two levels to all heights	4800 Nos	each		
2	Cleaning of Dholpur stone tiles upto all heights by washing with detergent/cleaning powder & scraping the surface, brush, sand paper etc i/c the cost of Jhoola and all other safety arrangements complete as per the direction of Engineer-in-charge.	450.00	Sqm		