

BY SPEED POST

**OFFICE OF THE EXECUTIVE ENGINEER
DELHI DEVELOPMENT AUTHORITY
SOUTH WESTERN DIVISION NO. 7
CENTRAL NURSERY :SECTOR-5 :DWARKA**

No. : F.67(814)EE/SWD-7/A/DDA/2013-14/699

Date : 29/6/13

To

M/s. Kushal Enterprises.
Shop No.1M- Block Market
Vikas Puri,
New Delhi.

Name of Work :- M/o Various Colonies under Dwarka Zone. Nazul A/C-II.
Sub Head:- Covering of damaged drain slabs with RCC and P/F missing SFRC covers from round about Sectors, 3-13 to Kakrola mor along Road No.201.
Estimated Cost;- Rs. 10,66,852/-
Ref: Your Performance Guarantee received vide F.D.R. No. 142446 dt. 26.06.2013 for Rs. 65000/- of The State Bank of Patiala, Dwarka, New Delhi-110077.

Dear Sir(s),

Your item rate tender dated 06.06.2013 for the above mentioned work has been accepted on behalf of Delhi Development Authority at the rates, terms and conditions given below :-

1	Estimated Cost .	Rs.10,66,852/- (Rs.Ten Lacs Sixty Six Thousand Eight Hundred Fifty two Only.)
2	Contractor's Quoted Amount	Rs. 12,71,560/- (Rs. Twelve Lacs Seventy One Thousand FiveHundred Sixty Only.
3	Contractor's Negotiated Accepted amount	Rs. 12,62,920/- (Rs. Twelve Lacs SixtyTwo Thousand NineHundred Twenty Only.

The percentage to be taken for the purpose of clause-12 shall be 18.38%(Eighteen point ThreeEight percent) above the estimated cost.

You are requested to attend the office of the undersigned alongwith non-judicial stamp paper worth Rs. 50/- (Rs. Fifty only) within seven days from the date of issue of this letter to sign the formal agreement failing which the acceptance of tender is likely to be withdrawn and earnest money be forfeited.

Please note that the time allowed for the completion of work as entered in the tender shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

The time allowed for execution of work will be two months.

P.T.O.

P-2

This office letter Nos. F.67(814)EE/SWD-7/A/DDA/2013-14/649 dt. 17.06.13 shall also form part of the agreement.

You are requested to contact Asstt. Engineer -III of this division and start the work immediately.

Encl : Schedule of Quantities.


Yours faithfully,

(R.K. Singh)
Executive Engineer,
South Western Divn.7,
D.D.A., New Delhi.

N.O.O.

Copy to :-


3. The Chief Engineer(Dwk)/DDA for kind information please.
4. SE/CC-2, DDA for kind information alongwith schedule of quantities.
3. Dy. CAO(CAU)DWK, DDA.
4. F.O. to CE(DWK)/DDA.
5. All EEs(Dwarka Zone)/DDA.
6. EE(QAC)-III/DDA.
7. A.O.(Works)-II/DDA.
8. Income Tax Officer, Contractor Cell, Addl./JCIT, Range-38, Room No. 236-A, C.R. Building, I.P. Estate, New Delhi-110001.
9. Labour Commissioner-I, Rajpur Road, Delhi-110054.
10. Dy. Commissioner, Sales Tax, Govt. of NCT of Delhi, Room No. 211, Bikrikar Bhawan, I.T.O., New Delhi-110001.
11. AE(P)/AAO/H.C./SWD-7, DDA.
12. AE- III/SWD-7, DDA for information & necessary action alongwith schedule of quantities.
13. Copy of Agreement.
14. Director (System) for website of DDA, Vikas Sadan, New Delhi.
ddatender @ dda.org.in.


Executive Engineer,
South Western Divn.7,
D.D.A., New Delhi.

116

DELHI DEVELOPMENT AUTHORITY						
Name of work:-M/o various colonies under dwarka Zone Nazul a/c-II.						
SH:- Covering of damaged drain slab with RCC and P/F missing SFRC covers from round about Sector-3-13 to kakrola Mor along Road No. 201.						
SCHEDULE OF QUANTITIES						
NIT No:- 3/EE/SWD/7/DDA/2013-14						
Estimated Cost: Rs. 10,66,852/-						
NAME OF THE FIRM				M/S KUSHAL ENTERPRISES		
S. No.	Description of item	Qty	Unit	Rate.	Rate in words	Amount.
	Providing and laying in position ready mixed concrete manufactured in fully automatic batching plant and transported to site of work in transit mixer for a lead up to 10kms having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering, shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS : 9103 to accelerate/retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. M-25 grade Reinforced cement concrete by using 410kg of cement per cum of concrete. All works up to floor V level.	80.00	Cum	5050.00	Rupees Five Thousand Fifty Only	404000.00
2	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. a).Thermo-Mechanically Treated bars.	9600.00	Kg	55.00	Rupees Fifty Five Only	528000.00
3	Centering and shuttering including strutting, propping etc. and removal of form for : a). Suspended floors, roofs, landings, balconies and access platform.	392.00	Sqm	190.00	Rupees One Hundred Ninety Only	74480.00
4	Providing and fixing of manhole covers with frame (SFRC) 560mm dia meter (Extra heavy duty HD 35)	24.00	Each	1250.00	Rupees One Thousand Two Hundred Fifty Only	30000.00
5	providing and fixing SFRC covers heavy duty 100mm thick procured from approved firm like K.K., Hindustan, Nitco, Nirco etc. and conforming to IS 12552 cover the opening of S.W. drain as per direction of Engineer-in-charge.	120.00	Sqm	1500.00	Rupees One Thousand Five Hundred Only	180000.00
6	Brick work with FPS Bricks of class designation 75 in foundation and plinth in cement mortar 1:4 (1 cement : 4 coarse sand).	12.00	Cum	3000.00	Rupees Three Thousand Only	36000.00

7	12mm cement plaster finished with a floating coat of neat cement of mix 1:3 (1 cement :3 fine sand)	99.00	Sqm	120.00	Rupees One Hundred Twenty Only	11880.00
8	Disposal of malb/earth etc. including loading unloading by mechanical transport with all leads and lifts.	80.00	Cum	90.00	Rupees Ninety Only	7200.00
Total						1271580.00


Executive Engineer
S.W.D.-7/D.D.A.
Central Nursery, Sec-5,
Dwarka, New Delhi-75