

**DELHI DEVELOPMENT AUTHORITY  
HARI NAGAR SPORTS COMPLEX**

**E-TENDER NOTICE NO. 06 /HNSC/DDA/2012-13**

Sealed item rate Tenders are re- invited for the following work by the undersigned on behalf of Delhi Development Authority, (Sports Wings) from the approved contractor of appropriate class of DDA C.P.W.D Railways, MES and P & T.

Tender documents can be obtained / downloaded on the e-tendering portal i.e. [www.tenderwizard.com/DDA](http://www.tenderwizard.com/DDA) or [www.dda.org.in](http://www.dda.org.in) up to **01.11.2012 (last date of sale)**. Earnest money amounting to ₹. 3105/- and cost of tender document of ₹. 525/- (Non-refundable) shall be deposited through RTGS/NEFT in the account of Hari Nagar Sports Complex, DDA. The unique transaction reference of RTGS/NEFT shall have to be uploaded by the tenderer in the E-Tendering system by the prescribed date. The DDOs concern will get tender cost/ earnest money verified from their banks based on the unique transaction reference no. against each RTGS/NEFT payment before the tenders are opened.

The unique transaction reference of RTGS/NEFT against EMD, Cost of Tender Document shall be placed in single sealed envelope superscripted as **“Earnest money, cost of Tender Documents”** with name of work and due date of opening of the bid mentioned there on and will submit to tender opening Authority by prescribe Date.

**ESTIMATED COST - ₹. 1,55,249/-**

SL.	<u>NIT No.</u>  Name of work	Name and Address of Sports Complex	Cost of Tender	Period of Contract	Last date and time of submission of tender	Date and time of opening of tender	Bank Detail
	Tender Processing Fee		Period During which unique transaction Reference of RTGS/NEFT against EMD, Cost of Tender document, E-tender processing fee and other document shall be submitted				
	Earnest Money						
1.	<u>NIT No.</u> <u>HNSC/DDA/2012-13</u>  N.O.W. Upgradation /Renovation of Existing facility at HNSC.  SH:- Renovation of Existing Reception by providing aluminium windows, painting, Tiles etc. in HNSC.	Hari Nagar Sports Complex	₹. <u>525/-</u>  ₹. <u>562/-</u>  ₹. <u>3105/-</u>	30 Days	<u>05.11.2012</u> At 3:00 PM  <hr/> <u>05.11.2012</u> At 3:00 PM	<u>06.11.2012</u> At 3:30 PM	Bank A/c No: - <b>0040104000200004</b>  Name of Bank: - <b>IDBI, Bank</b>  Branch Name : - <b>Rajouri Garden</b>  IFSC Code: - <b>IBKL 0000040</b>

-Sd/-  
**Commissioner (Sports)**  
**Delhi Development Authority**

**NOTE:** - For eligibility criteria, mode of payment of tender cost, processing fee, earnest money and other details of the tender visit the website [www.tenderwizard.com/DDA](http://www.tenderwizard.com/DDA) or [www.dda.org.in](http://www.dda.org.in). For any assistance on e-tendering please contact M/s ITI Limited on 011-49424365, 8800991856, 8800991864, 8800991859, 9971662903, 8800991851, 8800991861 and Fax 011-25618721.

No. F7(255)2011/HNSC/DDA/491

Date: - 18.10.2012

**Copy to:-**

1. Director (System), DDA with the request to bring the NIQ on DDA's Web-site through E-Mail-[ddatender@dda.org.in](mailto:ddatender@dda.org.in)
2. A. O. (Sports), DDA.
3. Secretary (Coordn.), Sports Wing, DDA
4. All Secretaries of the DDA Sports Complex
5. Secretary, DDA Contractor's Welfare Association, F-18, Vikas Kuteer, New Delhi.
6. Delhi Contractor's Welfare Association (Regd.), 306, Masjid Moth, N.D.S.E., Part-II, New Delhi-110049.
7. AAO (HNSC), DDA.
8. Manager (HNSC), DDA.
9. J.E. (Civil)/HNSC, DDA.
10. Notice Board (HNSC)

**Commissioner (Sports)**  
**Delhi Development Authority**

## SCHEDULE

### NAME OF WORK-UPGRADATION/ RENOVATION OF EXISTING FACILITY AT HNSC

### SH:- RENOVATION OF EXISTING RECEPTION BY PROVIDING ALUMINIUM WINDOWS, PAINTING, TILES ETC. IN HNSC

S.NO	PARTICULARS OF ITEMS	QTY	UNIT	RATE	AMOUNT
1.	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 mtr lead as per direction of Engineer –in-charge. In Cement mortar	2.00 m <sup>3</sup>	Cu.m		
2.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 mtr lead.	8.50m <sup>2</sup>	Sq.m		
3.	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave hold fasts etc. complete and stacking within 50 mtr lead: Of area 3 sq.mts. and below.	8.00 Nos	Each		
4.	Dismantling steel work in built up section in angles, tees, flats and channels i/c all gusset plates bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 mtr lead.	100.00 kg	Kg		
5.	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 mtr. All kinds of soil.	2.00 m <sup>3</sup>	Cu.m		
6.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- All work upto plinth level:				
(a)	1:5:10 (1cement: 5 coarse sand: 10 graded stone aggregate 40 mm nominal size).	2.00 m <sup>3</sup>	Cu.m		
(b)	1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	1.50 m <sup>3</sup>	Cu.m		
(c)	1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size).	1.00 m <sup>3</sup>	Cu.m		
7.	Brick work with F.P.S bricks of clars designation 75 in foundation and plinth in : Cement mortar 1:4 (1 cement : 4 coarse sand)	4.00 m <sup>3</sup>	Cu.m		
8.	Brick work with F.P.S bricks of clars designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement :4 coarse sand)	2.50 m <sup>3</sup>	Cu.m		
9.	12mm Cement plaster of mix: 1:4 (1 cement :4 coarse sand)	22.00 m <sup>2</sup>	Sq.m		
10.	15 mm Cement plaster on rough side of single or half brick wall of mix: 1:4 ( 1cement : 4 coarse sand)	22.00 m <sup>2</sup>	Sq.m		
11.	Providing & fixing Aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular section/ appropriate Z sections and other sections of approval make conforming to 15:733 and 15:1285, fixed with roof plugs, screws or with fixing clips, or with expansion hold fasteners	66.00 kg	Kg		

	including necessary filling up of gaps at junctions, at top, bottom & sides with required PVC/neoprene felt etc. Aluminium section shall be smooth, rust free, straight mild and jointed mechanically wherever required i/c cleat angle, Aluminium snap beading for glazing/ paveling. C.P. brass/ stainless screws all complete as per architectural drawing and as per direction of Engineer-in- charge. (Glazing and paveling to be paid for seperately): For fixed position: Anodized Aluminium				
12.	Providing & fixing glazing in Aluminium doors, windows, ventilators shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic items): With float glass panes of 5.50 mm thickness.	15.50 m <sup>2</sup>	Sq.m		
13.	Reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete: TMT Bars (Thermo-Mechanically Treated Bars).	41.00 kg	Kg		
14.	Centring and shuttering including strutting, propping etc. and removal of form for : (a) Shelves (cast in situ).	3.00 m <sup>2</sup>	Sq.m		
15.	Providing and fixing 18 mm thick gang saw cut mirror polished premoulded and prepolished machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 ( 1 cement : 4 coarse sand) with joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edge to give high glors finish etc. complete at all levels. Granite of any colour and shade. Area of slab over 0.50 Sq.m.	8.50 m <sup>2</sup>	Sq.m		
16.	Providing and Applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	134.00 m <sup>2</sup>	Sq.m		
17.	Finishing walls with Deluxe Multi surface point system for interiors and exteriors using Primers as per manufacturer specifications: Two or more coats applied @ 1.25 ltr/10 Sq.m over and including one coat of special primer applied @ 0.70 ltr/ 10 Sq.m.	134.00 m <sup>2</sup>	Sq.m		
18.	Providing sand stone slab for roofing and laying them in cement mortar 1:4 ( 1 cement : 4 coarse sand) over wooden karries or R.C.C battens (Karries and R.C.C battens to be paid separately) including pointing the ceiling joints with cement mortar 1:3 (1 cement : 3 fine sand) complete: Red sand stone slab 40 to 50 mm thick.	7.00 m <sup>2</sup>	Sq.m		
19.	Structural steel work in single section fixed with or without connection plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	100.00 kg	Kg		
20.	6 mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	14.00 m <sup>2</sup>	Sq.m		
21.	Providing and fixing Acoustical Radar Mineral fiber false ceiling including aluminium tee to form a grid of 600 x 600 mm centre to centre consisting of main "T" runner suitable spaced at joints to get the required	7.00 m <sup>2</sup>	Sq.m		

	length spaced at 1200mm c/c and cross "T" of 1200 mm long spaced between main "T" at 600 mm c/c to from a grid of 1200 x 600mm and secondary cross "T" of length 600mm to be interlocked in the middle of 1200 x 600 mm panel to from grids of 600 x 600 mm and laying false ceiling tiles of approved texture in the grid including whenever required cutting/making, opening for service like diffusers, light fitting, smoke detector etc consisting of the aluminium beading as per direction of the Engineer – in –charge.				
22.	Painting with Synthetic enamel paint of approved brand and manufacture to give an even shade : (a) One or more coats on old work. (b) Two or more coats on new work.	7.00 m <sup>2</sup> 13.50 m <sup>2</sup>	Sq.m Sq.m		
23.	Disposal of Malba, Like, building rubbish Moorum, lime etc. i/c stacking, loading & unloading by mechanical means within a lead of 5 Kms. as per direction of Engg- in -charge.	25.00 m <sup>3</sup>	Cu.m		
24.	Providing and fixing 1 <sup>st</sup> quality ceramic glazed wall tiles conforming to 15:15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engg-in-charge in skirting, risers of steps and dados over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per Sq.m including pointing in white cement mixed with pigment of matching shade complete.	18.50 m <sup>2</sup>	Sq.m		
25.	Providing and laying ceramic glazed floor tiles 300 x 300 mm (thickness to be specified by the manufacturer) of 1 <sup>st</sup> quality conforming to 15:15622 of approved make in colours such as white, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc. complete.	21.00 m <sup>2</sup>	Sq.m		
26.	Providing and laying four courses water proofing treatment with bitumen felt over roofs consisting of first and third courses of blown bitumen 85/25 or 90/15 conforming to 15:702 applied hot @ 1.45 kg per square mtr of area for each course, second course of roofing felt type 3 grade-1 (hessian based self finished bitumen felt) and fourth and final course of stone grit 6 mm and down size or pea-sized gravel spread at 6 cubic diameter per square mtr./c preparation of surface but excluding the grading complete with. Bitumen felt (hessian base) type 3 grade I conforming to 15: 1322.	23.00 m <sup>2</sup>	Sq.m		
27.	Supplying and fixing stainless steel pipe of dia. 100 mm used vertical and dia of 75 mm used horizontal in between two pipe including materials, labour etc, complete job work (cost of excavation and cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm n/size to be paid separately) as per direction of Secretary/ HNSC and JE (Civil).	10.00 m	Mtr.		