

DELHI DEVELOPMENT AUTHORITY
SOUTH EASTERN DIVISION NO. XI

NOTICE INVITING TENDER

Sealed item rate tender are invited for the following works by the Executive Engineer/SED- XI, Vikas Sadan, INA upto 3.00 PM on behalf of DDA from the approved contractors of appropriate class of DDA, CPWD, MES, P&T & Railway on the dates mentioned below which shall be opened on the same day at 3.30 P.M at Vikas Sadan (Press Building) near INA Market, New Delhi in the presence of intending purchase of their authorized representatives.

The tender documents can be obtained on any working day from the CAU (SEZ) Sale counter, Press Building, Vikas Sadan between 11.00 AM to 3.00 PM on payment of cost of tenders (non-refundable) as well as amount of Earnest Money mentioned against each work on production of valid Enlistment Certificate and valid certificate of Registration with work contract cell of Sale Tax Deptt of GNCTD & Tax clearance certificate issued by the Work Contract Cell. Sale of tender forms will be stopped four days (including the date of opening) before the date fixed for the opening of tender documents.

The earnest money should accompany the tender application in the form of a Call deposit receipt or demand draft of a Schedule Bank guaranteed by the Reserve Bank of India in favour of A.O (CAU) SEZ/DDA.

S.No.	NIT No.	Name of work	Estt. cost Earnest Money Cost of tender	Last dt. of Sale Dt. of Opening Time allowed
1.	26/EE/SED- XI/DDA/07-08	(Re-invited) M/O Various colonies under SEZ. SH: P/F of doors litters and other misc. work at C/O 360 MIG houses in Sec.14, Pkt. B, Dwarka, Ph-II.	Rs. 1,70,379/- Rs. 3,408/- Rs. 500/-	05.10.07 09.10.07 1 month
2.	27/EE/SED- XI/DDA/07-08	(Re-invited) M/O Compl. scheme finishing & furnishing i/c T.C. etc. Complete at Vikas Sadan. SH: Scavenging of circulation area upkeep of drainage system at Vikas Sadan.	Rs. 1,71,348/- Rs. 3,427/- Rs. 500/-	05.10.07 09.10.07 6 Months.
3.	32/EE/SED- XI/DDA/07-08	-DO- SH: M/O road footpaths & Bus shelter in circulation area around Vikas Sadan.	Rs. 1,83,706/- Rs. 3,674/- Rs. 500/-	05.10.07 09.10.07 6 Months

No. F-5 (471, 472, 473) SED- XI/DDA/A/07-08/ 610

Dt. 26/9/07

EXECUTIVE ENGINEER/SED- XI

26/9/07

Cont.....2/-

Copy to:

1. CE(SEZ) DDA 2. SE, CC-16 3. Director (System) DDA for placing it in Web site of DDA 4. FO to CE(SEZ) 5. PAO(EW) DDA 6. AO(W) I 7. DDA Contr. Association (Regd) 40-A Vikas Minar 8. In. Tax Officer Contr. Circle ITO 9. Contr. Association, CPWD Y-Shape Bldg. 10. Contr. Welfare Association (Regd) 12. A Barrack No.1 Blk A Vikas Kuteer 11. Labour Commissioner, Rajpura Road 12. All EEs/DDA. 13. EE/WD-12 14. All AEs/SED-XI 15. Chief Security Officer/DDA 16. HC/SED-XI 17. Tender clerk, Centralised Tender Office, Vikas Sadan 18. Delhi Contr. Welfare Association, 2613, Gali Dharamshala Wali, Kali Masjid, Rukman Gate. 19. AO CAU (SEZ), Shahpurjat, 20 Delhi Contr. & Builder Association, H.NO. 5508, Ch. Prem Singh Bhawan, New Chandrawal, Ch. Bhim Singh Road 21. Trans Yamuna DDA Contr. Association (Regd) Gandhi Nagar. 22. Dy. Commissioner (Work Contract) Bikri Kar Bhawan I.P. Estate 23. Notice Board of SED-XI 23. Cashier/SED-XI/DDA 25. Delhi Govt. Contractors Welfare Assn (Regd) 174, Trivent Apptt near Police Stn. Vivek Vihar Delhi-110095. 26. DDA web site dda tender @dda.org.in & Dir system dirsystem@dda.org.in.

EXECUTIVE ENGINEER/SED-XI

26/9/08

26/9/08

SCHEDULE OF QUANTITIES

NAME OF WORK
SUB-HEAD

: M/O VARIOUS COLONIES UNDER S.E.Z.
Providing and fixing of door shutters & other miscellaneous works at 360 MIG Houses in Sector-14, Pocket-
B. Dwarka Phase-II

Estt. Cost Rs 1,70,379/-
@ 17% Rs 3408/-
Time Allowed = One Month.

S.No.	Description of item	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1.	Providing & fixing panelled or paneled and glazed shutters for doors windows & clestory windows i/c S.I. marked black enameled M.S. butt hinges with necessary screws excluding paneling which will be paid separately. (a) Kiln seasoned & chemically treated hollock wood.	70.00	Sqm		
2.	Deduct for providing & fixing ISI marked M.S. pressed butt hinges bright finished with necessary screws etc. complete (a) 100x58x1.90mm	156.00	Each		
3.	Providing & fixing paneling or paneling and glazing in paneled or paneled and glazed shutters for doors windows and clestory windows (area of opening for panels inserts excluding portion inside groove or rebates to be measured, paneling or paneled and glazed shutters 25mm to 40mm. (a) Kiln seasoned & chemically traded hollock wood.	33.00	Sqm		
4.	Providing and fixing Fly proof galvanized M.S. wire gauge to windows and clestory windows using galvanized M.S. wire gauge with average width of aperture 1.4mm in both directions with wire of dia 0.63mm. With 2 nd class teak wood beeding 62x19mm.	7.00	Sqm		
5.	Providing & fixing ISI marked flush doors shutters non-decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bends and face veneers on both faces of shutters. (a) 30mm thick including ISI marked stainless steel butt hinges with necessary screws.	49.00	Sqm		
6.	Deduct for providing and fixing ISI marked aluminium butt hinges ISI marked anodized (Anodic coating not less than grade A.C. 10 as per IS 1868) transparent or dyed to required colour or shade with necessary screws etc. complete. (a) 100x63x4mm	120.00	Each		

7.	Applying priming coat with ready mixed pink or gray primer of approved brand and manufacture on wood work (hard & soft wood)	299.00	Sqm		
8.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade (a) Two or more coats on new work	299.00	Sqm		
9.	Providing & fixing aluminium sliding door bolts ISI marked anodized (anodic coating not less than AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts & screws etc. complete (a) 300x16mm	8.00	Each		
10.	Providing & fixing aluminium tower bolt ISI marked anodized (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc. complete (a) 250x10mm (b) 150x10mm	64.00 64.00	Each Each		
11.	Providing and fixing Aluminium handle ISI marked anodized (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc. complete (a) 100mm	158.00	Each		
12.	Providing and fixing ISI marked 85mmx42mm oxidized M.S. pull bolt, lock confirming to IS:7534 with necessary screws bolts, nuts & washers etc. complete	67.00	Each		
13.	Renewing glass panes, with putty and nails where ever necessary. (a) Glass panes weighing 10 kg/sqm	96.00	Sqm		

SCHEDULE OF QUANTITIES

Name of Works:- M/O Completed Scheme financing & flushing I/c E.C etc. complete at Vikas Sadan.

SH:- Scavenging of circulation area up keep of drainage system at Vikas Sadan.

Estt. List No 1 71348-2
E.M.
Rs 3427-
Time Allowed - 6 months

S.No.	Desc. of Items.	Qty.	Unit	Rate	Amount
1.	Cleaning and sweeping of roads, path etc. I/c collecting night soil from malba dead animals I/c cleaning of cleaning of dustbins carrying out the soil refuse from site to dumping grounds as per the direction of engineer-in-charge.	180 days.	per day		
2.	Carriage/disposal of merum building rubbish garbage malba night soil, dead animals refuse etc. by mechanical transport including (loading unloading & leadup to 13 Km.	180 days	per day		
3.	Cleaning and dumping of signage removing bill poster from walls of bus stand removing dropping from soil pastures etc. on up graded roads around Vikas Sadan I/c mopping of sitting places of bus stand and planter area (once in a week).	6 month	per month		

SCHEDULE OF QUANTITIES

NAME OF WORK : M/O Completed scheme finishing and furnishing i/c T.C. etc. complete at Vikas Sadan

SUB-HEAD : Maintenance of Road Footpaths and Bus Shelters in circulation area around Vikas Sadan

S.No.	Description of Item	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1.	P/F machine made Kerb stone of size 300x300x150mm with or without cavity on one side of kerb stone, manufactured by using M-25 grade concrete using GRF moulds by vibro-compaction process as to achieve shutter finish on front face, as per the sample approved by Engineer-in-charge including fixing with 10mm thick cement mortar 1:3 (1 cement : 3 coarse sand) at bottom and jointing with 1cm cement mortar (1 cement : 3 fine sand) including making drainage opening wherever required. as per direction of Engineer-in-charge.	40.00	Per Mtr.		
2.	Random Rubble Masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20mm nominal size) at plinth level with cement mortar 1:6 (1 cement : 6 coarse sand)	10.00	Cum		
3.	Kota stone slab flooring over 20mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand) 25mm thick	43.00	Sqm		
4.	40mm thick fine dressed and rubbed stone flooring over 20mm (average) thick base with joints 5mm thick finished flush, base with 1:5 (1 cement : 5 coarse sand) (a) Red sand stone	50.00	Sqm		
5.	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) (a) Ruled pointing	50.00	Sqm		

6.	Providing and laying Pre-cast cement inter-locking pavers 60mm thick having minimum compressive strength 250kg/ cm ² including setting in position, filling joints with Yamuna sand, breaking and end cutting, leveling to finish and compaction etc. all complete as per direction of Engineer-in-charge. (a) Medium duty blocks of M-25 grade, 60mm thick of natural grey colour without pigment.	105.00	Sqm		
7.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work upto plinth level. (a) 1:2:4 (1 cement : 2 coarse sand : 4 gr. stone agg. 20mm m.s.) (b) 1:5:10 (1 cement : 5 coarse sand : 10 gr. stone agg. 40mm m.s.)	4.00 16.00	Cum Cum		
8.	Supplying and fixing of Cylindrical precast reinforced cement concrete bollards of height 950mm and dia 150mm with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone agg 20mm nominal size) including excavation of holes etc. complete as per direction of Engineer-in-charge (payment for cement concrete shall be made separately)	30.00	Each		
9.	Brick work with FPS bricks of Cd 75 in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand)	7.00	Cum		
10.	12mm cement plaster of mix (a) 1:4 (1 cement : 4 coarse sand)	65.00	Sqm		
11.	Supplying and placing in position rectangular S.F.R.C. cover for S.W. drain chambers having concrete mix M-30 encased with 14 S.W.G.M.S. sheet channels consisting of reinforcement of 8mm dia, bearing welded from inside to the wall of encasing sheet. The encasing sheet shall be painted with bitumen paint. The cover shall be provided with 2 Nos. 12mm dia lifting hook, flushing with top surface of cover. (a) 50mm thick with or without holes of 50mm dia width of cover shall not be more than 450mm.	14.00	Each		
12.	Providing and fixing hand rail by welding etc. to steel ladder railing, balcony railing and staircase railing including applying a priming coat of approved primer (a) M.S. Tube (medium) 50mm nominal bore	322.00	Kg		

13.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give and even shade (a) One or more coat on old work	165.00	Sqm			
14.	Coursed stone masonry with hand chiseled dressed stone (Delhi Quarry) in foundation and plinth in cement mortar 1:6 (1 cement : 6 coarse sand) including ruled pointing with cement mortar (1 cement : 3 fine sand) complete as per direction of Engineer-in-charge.	2.00	Cum			
15.	Disposal of building rubbish by mechanical transport including loading, unloading and stacking for at lifts as per direction of Engineer-in-charge. <i>all leads 24</i>	51.00	Cum			

NOTE :- Cement 6.28 M.T. @ Rs. 4600/- per M.T. shall be issued from any D.P. & Store Delhi / New Delhi.