

OFFICE OF THE EX. ENGINEER
SOUTH EASTERN DIVISION : 11
D.D.A.:VIKAS SADAN:INA:N.D.

No. F5(464) SED. XI/A/DDA/2007-08/ 551

Dated: 14/9/07

To

M/s. Civil Construction Co.,
D-36, DDA Flats, Saket,
New Delhi-110 007.

SUB.: D/o Land for B.A Distt. Centre at Saket.
SH : C/o Boundary wall for site office

D/Sir,

Your negotiated item rate tender for the above noted work has been accepted on behalf of DDA subject to the terms and conditions given below:-

1. Estimated Cost : Rs.4,58,644.00
(Rs.Four lacs fifty eight thousand six hundred forty four only)
2. Contractor's %age(for the purpose of clause-: 42.14% above on DSR - 2002 12)
3. Tendered Amount : Rs.6,51,937.00
(Rs.Six lacs fifty one thousand nine hundred thirty seven only)

You are requested to attend this office alongwith non-judicial stamp paper worth Rs.50/- and sign the agreement within seven days from the date of issue of this letter failing which acceptance of your tender is likely to be withdrawn and the earnest money shall be forfeited.

You are also directed to contact the Asstt. Engineer-IV, SED.11 and start the work atonce. Please note that the time allowed for carrying out the work as entered in the tender form shall be reckoned from 10th day after the date of issue of this letter to commence the work.

The time allowed for execution of the work will be one month. Your letter No.Nil dated 7.8.07 shall be part of the agreement.

Yours faithfully,

(A.K. MALIK)

EX. ENGR./S.E.D.11:DDA

COPY TO:-

1. C.E. (SEZ) DDA 2.S.E./CG-16/DDA 3. F.O. to C.E. (SEZ) 4.PAO(EW)
5. A.O.(W) I 6. Income Tax Officer, Cont. Circle, ITO, N.D. 7. All
- EEs/DDA 8. All AEs/SED.11 9. AE(P)/SED-11 10. The Labour Commission
11. A.O(CAU) DDA 12. The Dy. Commissioner (Work Contract) Bikri Kar Bhawan, I.P. Estate, New Delhi 13. For agreement
- SED-11 14. AE-IV/SED-11/DDA alongwith schedule with the direction report to this office within ten days whether the contractor has taken over the site for executing the work. 15. Cashier/SED-11 16. EE(AC)
- DDA 17. Security Officer, Vikas Sadan 18. ddatander@dda.org.in & dirsystem@dda.org.in.

EX. ENGINEER: SED - 11
D.D.A.

SCHEDULE OF QUANTITIES

NAME OF WORK : D/O LAND FOR DISTRICT CENTRE AT SAKET

SUB-HEAD : C/o Boundary Wall for Site office

S.No.	Description of Item	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1.	Earth work in excavation in foundation trenches & drains (not exceeding 1.5m in width & 10sqm or plan) including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m. (a) All kind of soil	67.00	Cum	128-00	8576-00
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work up to plinth level : 5:10 (1 cement : 5 coarse sand : 10 graded stone agg 40mm M.S.) F.P.S	49.00	Cum	2100-00	102900-00
3.	Brick work with bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	31.00	Cum	2000-00	62000-00
4.	Brick work with flyash bricks of class designation 75 in superstructure above plinth level upto floor five level in cement mortar 1:6 (1 cement : 6 coarse sand)	47.00	Cum	2140-00	100580-00
5.	Providing and laying in position cement concrete of specified graded excluding the cost of centring and shuttering – all work upto plinth level. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone agg 20mm nominal size)	5.00	Cum	2800-00	14000-00
6.	Washed stone grit plaster an the ext walls of height upto 10 m. above level in two under layers 12mm cement plaster 1:4 (1 cement : 4 coarse sand) furrowing the under layer with scratching tool, applying cement on the under layer @ 2 kg of cement per sqm, top layer 15mm cement plaster 1:1/2:2 (1 cement : 1/2 coarse sand : 2 stone chipping 10mm nominal size) in panels with grave all around as per the approved pattern including scrubbing and washing the top layer with brush and water to expose the stone chipping. Complete as per specification and direction of engineer-in-charge (payments for providing grooves shall be made separately).	342.00	Sq.mt.	300-00	102600-00

	Structure steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a primary coat of approved steel primer all complete.	2321.00	Per kg	43-10	99803-00
8.	Providing and laying inter locking pre-cast, CC Paver Blocks of approved designs in pavements, parking etc. i/c setting in position over average 50mm thick bed of Jamuna sand, filling joints with Jamuna sand i/c leveling of bed and compaction with wooden rammer etc. all complete as per direction of engineer-in-charge	406.00	Sqm	369-00	149814-00
(a)	60mm thick cement concrete paver block of required colour having composite strength 250kg/cm ² & above.				
9.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade in two or more coats on new work.	84.00	Sqm	32-00	2688-00
10.	Centring and shuttering including strutting, propping etc. and removal of form for (a) Foundations, footings, base of column etc. for mass concrete.	20.00	Sqm	90-00	1800-00
11.	Forming groove of uniform size in the top layer of washed stone grit plaster as per the approved pattern using wooden battens, nailed to the under layer including removal of wooden battens, repairs to the edges of panels and finishing the groove complete as per specification and direction of the Engineer-in-charge. 15mm wide and 15mm deep groove.	552.00	metre	13-00	7176-00

NOTE :- Cement 19.00 MT. @ R. 4600/- per MT.

Shall be issued from my P.D.A store
Delhi / New Delhi;

Total Rs 651,937-00

Signature
South
Delhi
6/11/21